

Appendices

Appendix A

Work Plan



AOI 8 RFI Tasks Workplan

Marcus Hook Industrial Complex
Marcus Hook, Pennsylvania

Evergreen Resources Group, LLC

410 Eagleview Boulevard, Suite 110 Exton, Pennsylvania 19341
11102524 | Report No 1 | March 18, 2016

Table of Contents

Contents

1.	Introduction	1
2.	Scope of Work	1
2.1	Drilling Site Inspection	1
2.2	Health and Safety	1
2.3	Well Installation	1
2.4	Groundwater Sampling	2
2.5	Project Coordination	3
3.	Schedule	3

Figure Index

Figure 1 AOI-8 Proposed Locations

Table Index

Table 1 Summary of Proposed Site Characterization Activities AOI-8

Appendices

- Appendix A Underground Utilities Checklist
- Appendix B Job Safety Analyses

1. Introduction

GHD has prepared this groundwater monitoring well installation plan, on behalf of Evergreen Resources Group, LLC (Evergreen), for the evaluation of soil and groundwater contamination at the Braskem facility, AOI-8, Marcus Hook Industrial Complex, Marcus Hook, Pennsylvania.

Soil and groundwater will be evaluated and characterized on the site, and screened for direct contact medium specific concentrations (MSCs). The investigation aims to verify if contamination is migrating into AOI-8 from adjacent AOIs, and also to verify if any contamination from AOI-8 itself is migrating offsite.

This work plan presents the scope of work, schedule of activities, and reporting.

2. Scope of Work

The Scope of Work for AOI-8 RI is presented in Table 1 and locations are shown in Figure 1.

2.1 Drilling Site Inspection

Prior to drilling, GHD, Evergreen and Braskem personnel will walk the site and examine each of the five points where wells will be installed. GHD will check for visible evidence of utilities, examine maps of the facility, and discuss the drilling plan with site personnel. GHD will work with the drilling contractor Parratt-Wolff to complete One-Call Notifications on the proposed drilling locations and perform other utility reviews with Braskem as appropriate. As agreed with Braskem, GHD will contract a utilities locator service to mark underground utilities on the west side of the site and the western half of the front of the site where the Bear Creek storm sewer is known to run. Following utility mark out, a 'soft dig' will be performed at each of the drilling locations. Sweeney, a contractor at MHIC, will backhoe down to 8 feet to clear each of the locations. In addition, power lines run above several of the drilling locations. GHD will work with Parratt-Wolff to position the final locations so that the tower of the rig is sufficiently isolated from overhead lines. GHD will complete an Underground Utilities Checklist as shown in Appendix A.

2.2 Health and Safety

All contractors working with GHD and Parratt-Wolff will complete the Braskem safety training video. They will all have up to date PSM training and TWIC cards. All workers will be familiar with this Work Plan and Job Safety Analyses (JSAs, See Appendix B) prepared for the tasks involved in completing the work scope. Daily safety tailgate meetings will be conducted prior to start of work to review the tasks and hazards and means to mitigate risk of injury or property damage.

2.3 Well Installation

Five wells will be installed by Parratt-Wolff at the boundaries of AOI-8. Their locations were chosen to monitor for constituents of concern that may be migrating into the facility from adjacent AOIs, or to monitor downgradient groundwater flow across AOI-8 itself.

MW-571 will be installed in the northwest of the facility. GHD will collect soil samples from the excavated soils during 'soft dig' clearance. Upon attainment of the 8 foot depth, soils will be

backfilled and compacted with the excavator. MW-571 will later be drilled through the compacted backfill to depth. The target depth of all wells is 15 feet below ground surface. The well will be flush mounted to the surface.

MW-570 will be installed at the southwest corner of the facility, on the grass by 10th street. The Bear Creek storm sewer turns 90 degrees in this vicinity and runs approximately along the fence line. It is expected that there is sufficient space between Bear Creek and the street at this point. Following 'soft dig' clearance and soil sampling, the well will be installed as described above. The rig will access the site from 10th street. The monitor well will be installed through the compacted backfill to a nominal depth of 15 feet below grade and completed with a flush mount cover.

MW-569 will be drilled on the grass in front of the main office building. The Bear Creek storm sewer is expected to be closer to the street at this location. The well will be installed (following 'soft dig' clearance) between the sidewalk and the storm sewer. The rig will access the site from 10th street and will be parked over the mound formed by the Bear Creek culvert. The monitor well will be installed through the compacted backfill to a nominal depth of 15 feet below grade and completed with a flush mount cover.

MW-568 is to be installed in the southeast corner of the property. The drill rig will enter through the gate on Blueball Avenue near the intersection with 10th street. Following 'soft dig' clearance and soil sampling, the monitor well will be installed through the compacted backfill to a nominal depth of 15 feet below grade and completed with a flush mount cover.

Finally, MW-567 will be installed in the northeast of the facility, approximately 15 feet beyond Braskem's fence line. The drill rig will enter through the other gate on Blueball Avenue. The well will be drilled adjacent to the overhead pipes (at a specific location to be identified by an SXL representative) near the avenue towards the facility's inner fence. Sweeney will backhoe to 8 feet to verify that there are no underground utilities. The soils will be sampled and backfilled as described above. The monitor well will be installed through the compacted backfill to a nominal depth of 15 feet below grade and completed with a flush mount cover.

Drilling will be performed with a combination rig using direct push methods for soil sampling and a hollow stem auger for borehole advancement. Split spoons will be advanced to a depth of approximately 15 feet to acquire soil samples. Samples will be collected for analysis at the 0-2 feet below grade interval, and at the 2-15 feet below grade interval above the water table. Spoils/cuttings during monitor well boring will be collected and drummed and staged on the adjacent Sunoco property along Blueball Avenue. Evergreen will be responsible for removing and disposing of the drums.

Following well installation, the wells will be developed by overpumping and surging until generally free of suspended solids. Well development water will be collected in a container and managed with soil cuttings by Evergreen. The monitor wells will later be surveyed for location and reference point elevation by an Evergreen contractor.

2.4 Groundwater Sampling

Following monitor well installation and development the wells will be allowed to recover for two weeks. Groundwater sampling will be performed using low flow methods. Purging water will be collected and combined in a container on the adjacent Sunoco property (as for the soils described

above). Evergreen will be responsible for removing and disposing of the containerized development and purge water.

2.5 Project Coordination

GHD and Evergreen will be in contact with Braskem should any changes to the plan arise or problems occur.

3. Schedule

The activities proposed in this Work Plan will commence in April and be completed in May 2016. All Site-related activities will be conducted in accordance with GHD's Health and Safety Plan.

Laboratory results are expected to be received one month following submittal of samples to the laboratory. A summary of the results will be included in the RIR. The summary will include indoor air analytical data, QA/QC data and an assessment of the indoor air data.

Recommendations regarding the need to conduct further evaluation of the vapor intrusion pathway will be included in the RIR.



Source: AOlS and Remediation Systems - Stantec
Aerial: Microsoft product screen shot(s) reprinted with permission from Microsoft Corporation, June 2014

0 50 100 150
Feet



Coordinate System:
NAD 1983 StatePlane Pennsylvania
South FIPS 3702 Feet



EVERGREEN RESOURCES MANAGEMENT
PHILADELPHIA REFINERY OPERATIONS

AOI-8 PROPOSED LOCATIONS

11110315-00
Mar 3, 2016

FIGURE

TABLE 1

SUMMARY OF PROPOSED SITE CHARACTERIZATION ACTIVITIES
 AOI 8 WORK PLAN
 Marcus Hook Industrial Complex
 Marcus Hook, Pennsylvania

Location ID	Existing	Proposed	Estimated Completion Depth for Proposed Monitoring Wells and Soil Borings	Media	Collection of Surface Soil Sample (0-2 ft bgs) for Analytical Parameters in Table 2	Collection of Soil Sample from Soil/GW Interface for Analytical Parameters in Table 2	Collection of Groundwater Sample for Analytical Parameters in Table 2	Objective of Proposed Activity
MW-571		X	Screen Approximately 5-15 ft. bgs	GW/soil	X	X	X	Assess background impacts from adjacent areas
MW-567		X	Screen Approximately 5-15 ft. bgs	GW/soil	X	X	X	Assess background impacts from adjacent areas
MW-568		X	Screen Approximately 5-15 ft. bgs	GW/soil	X	X	X	Assess conditions for presence of NAPL from adjacent AOI 4
MW-569		X	Screen Approximately 5-15 ft. bgs	GW/soil	X	X	X	Downgradient well to assess impacts from AOI 8
MW-570		X	Screen Approximately 5-15 ft. bgs	GW/soil	X	X	X	Downgradient well to assess impacts from AOI 8

Table 2
Constituents of Concern for Groundwater
AOI 8
Marcus Hook Industrial Complex
Marcus Hook, Pennsylvania

METALS (dissolved)	CAS No.
Mercury	7439-97-1
Lead	7439-92-1
VOLATILE ORGANIC COMPOUNDS	
1,2-Dichloroethane	107-06-2
1,2,4-Trimethylbenzene	95-63-6
1,3,5-Trimethylbenzene	108-67-8
Benzene	71-43-2
Cumene	98-82-8
Ethylbenzene	100-41-4
Ethylene dibromide	106-93-4
Methyl tertiary butyl ether	1634-04-4
Toluene	108-88-3
Xylenes (total)	1330-20-7
SEMI-VOLATILE ORGANIC COMPOUNDS	
Anthracene	120-12-7
Benzo(a)anthracene	56-55-3
Benzo (g,h,i) perylene	191-24-2
Benzo(a)pyrene	50-32-8
Benzo(b)fluoranthene	205-99-2
Chrysene	218-01-9
Fluorene	86-73-7
Naphthalene	91-20-3
Phenanthrene	85-01-8
Pyrene	129-00-0
Other Parameters	
pH	-

Appendices

Appendix A

Underground Utilities Checklist

Underground Utilities Checklist

(QSF-019)

Pre-Drilling/Excavation Checklist and Utility Clearance Log

Project number:	Project name:
Date:	Project location:
Public utility locator:	Public utility locator phone number:
Date of public utility locator request:	Public locator call reference number:
Private utility locator (If applicable):	Private utility locator phone number:

Utilities (indicate that location/utility presence was checked)												
Borehole/ Excavation location	Date (mm/dd/yyyy)	Telephone	Water	Storm sewer	Sanitary sewer	Process sewer	Gas	Electrical	Cable	Overhead utilities	Other	Comments/Warnings
Utility owner:												

Instructions: This checklist is to be completed by GHD personnel prior to initiation of field activities as a safety measure, to ensure that all underground utility lines, other underground structures, and above-ground power lines are clearly marked in the area selected for boring or excavation.

Notes: _____

Client: _____ **Client representative:** _____ **Phone number:** _____

Client or property owner acknowledgement of utility clearance: _____ **(Client, property owner, or authorized agent signature)**

Subcontractor acknowledgement of utility clearance: _____ **(Subcontractor or subcontractor representative signature)**

GHD field representative name: _____ **Signature:** _____

GHD project manager's review/confirmation of locate completion: _____

In the event that client or property owner acknowledgement cannot be obtained, all boreholes shall be hydro vacuumed and the costs passed on to the client. Attach any clearance documentation from utility owner/operator to this document.

Underground Utilities Checklist for GHD Personnel

Pre-Drilling/Excavation Checklist and Utility Clearance Log

Drilling or excavation work may not proceed if any of the questions answered below are answered "No." Implement stop work authority and contact the GHD project manager to discuss and resolve any concerns or issues. Document the reason for a "No" answer in the comments section below.

Yes	No	N/A	
Pre-Mobilization			
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	1. Has a utility locator request been completed within the last 30 days (verify time limit with state or provincial law)? If no, stop work and comment below.
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	2. Is a scaled site plan, map or drawing showing the proposed borehole locations attached to this form?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	3. Does each borehole and excavation location allow for clear entry and exit, adequate workspace, and a clear path for raising the mast (or boom) and operating the drill rig and all support equipment? Ensure that the minimum OSHA/state/provincial utility clearance requirements between the mast or boom and the power line(s) are met. For instance, OSHA requires a minimum approach distance of 10 feet for systems below 50 kV and an increase of 4" for every 10 kV over 50 kV. Confirm if additional permits are required if the boom or mast will be working 5 meters (15 feet) or less from the electrical lines.
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	4. Are all of the proposed borehole and excavation locations at least 1.0 meters (3 feet) from any subsurface or above-ground utilities shown on client's building plans? Check here <input type="checkbox"/> if plans not provided by client (therefore not applicable to this job).
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	5. Are all of the proposed borehole and excavation locations at least 1.0 meters (3 feet) from any subsurface or above-ground utilities shown on public right-of-way street improvement or other public property plan or site map?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	6. Has the site representative, familiar with the site, indicated no knowledge of any subsurface or above-ground utilities within 3 metres (10 feet) of the proposed borehole and excavation locations? (Review locations with site representative)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	7. Are all of the proposed borehole and excavation locations at least 1.0 meters (3 feet) from any subsurface utilities identified during a geophysical survey? Check here <input type="checkbox"/> if no geophysical survey has been completed (therefore not applicable to this job).
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	8. Have all utility locating service providers, notified by the public line locator, marked out their facilities in the vicinity of the borehole and excavation locations or otherwise notified us that they do not have any facilities near the proposed locations? (Attached confirmation and utility locate sheets from public locator)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	9. Are all proposed borehole and excavation locations at least 1.5 meters (5 feet) from a visual line connecting two similar looking manhole covers?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	10. Are all proposed borehole and excavation locations at least 1.5 meters (5 feet) from a visual line perpendicular to the street from the water, gas, and electrical meters?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	11. Are all proposed boring and excavation locations clear of pavement joints, curbs, crash posts, or other engineered structures?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	12. Does the ground surface/pavement lack signs of previous excavation (e.g., no pavement subsidence, no differences in pavement texture or relief, no pavement patching)?
Pre-Drilling and Excavation			
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	13. Has it been verified that the proposed drilling or excavation work will not affect any work currently in progress?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	14. Has the drill rig or heavy equipment been inspected prior to use and documented? (See Drill Rig Inspection Checklist or Mobile Equipment Safety Inspection Checklist)
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	15. Have barricades been erected to prevent unauthorized access, where applicable?
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	16. Have all known live electrical or product lines within 3 meters (10 feet) of the dig path been visually verified? If no, comment below.
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	17. For boreholes that have not been cleared or are within 3 meters of a utility:
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	a. Before drilling have you cleared a hole to 2.4 meters (8 feet) below grade using an air-knife, or equivalent, before drilling and is the diameter of this hole greater than the final outside diameter of the boring? If not required comment below.
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	b. Does the soil you encountered in the hand-dug hole appear to be native material (i.e., free of clean gravel, clean sand, aggregate base [gravelly sand ~ 10% fines] or other non-native looking material)? If not required comment below.

Have the above concerns been discussed with the GHD project manager?

Have the start of subsurface work been communicated to the GHD project manager?

Have the above concerns been discussed with the client?

Has the scope of work been approved by the client?

<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Not Applicable
<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Not Applicable
<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Not Applicable
<input type="checkbox"/> Yes	<input type="checkbox"/> No	<input type="checkbox"/> Not Applicable

Comments: _____

GHD field representative name: _____

Date: _____

Appendix B

Job Safety Analyses



Job Safety Analysis (JSA)

Insert Name: Driving

Field staff must review job specific work plan and coordinate with project manager to verify that all up front logistics are completed prior to starting work including, but not limited to, permitting, access agreements, and notification to required contacts (e.g., site managers, inspectors, clients, subcontractors, etc.). Additionally, a tailgate safety meeting must be performed and documented at the beginning of each workday. **Stop, Think, Act, Review (STAR)** must be used prior to any activity. All personnel must possess the appropriate training prior to initiating scheduled tasks. Also consider weather conditions. GHD personnel have the authority and responsibility to use **Stop Work Authority (SWA)**.

Date Issued/Revised:	2/11/2016 6:22:21 PM	Client:	Evergreen Resources Management		
Project Number:	11109626	Created By:	cra\MMarcus	SIM OPS? YES/NO	SSE on site? YES/NO
Project Address:	3144 West Passyunk Avenue Philadelphia				
Key Equipment:	Vehicle, valid driver's license, 360 degree topper				
Task-specific Training:	Defensive Driving				

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Type I (Top Impact)	<input type="checkbox"/> Chemical Protective (ie. Nitrile)	<input type="checkbox"/> ANSI/CSA Safety Glasses	<input type="checkbox"/> Harness	<input type="checkbox"/> Full Face Mask	<input type="checkbox"/> Class II	<input type="checkbox"/> Coveralls
<input type="checkbox"/> Type II (Side Impact)	<input type="checkbox"/> Level 1 Light Duty	<input type="checkbox"/> Goggles/Spoggles	<input type="checkbox"/> Shock Absorb Lanyard	<input type="checkbox"/> Half Face Mask	<input type="checkbox"/> Class III	<input type="checkbox"/> Fire Retardant Clothing (FRC)
<input type="checkbox"/> Class E (standard)	<input type="checkbox"/> Level 2 Light Duty with Protection	<input type="checkbox"/> Face Shield	<input type="checkbox"/> Lifeline		<input type="checkbox"/> Anti-Static	<input type="checkbox"/> High Viz Clothing
<input type="checkbox"/> Class G	<input type="checkbox"/> Level 3 Medium Duty	<input type="checkbox"/> Other*		Cartridges	<input type="checkbox"/> FRC	<input type="checkbox"/> Long Pants
	<input type="checkbox"/> Level 4 Heavy Duty			<input type="checkbox"/> N95	<input type="checkbox"/> PFD	<input type="checkbox"/> Long Sleeve Shirts
Foot Protection	<input type="checkbox"/> High Viz	Hearing Protection	Arc Flash/Shock Protection	<input type="checkbox"/> P100		<input type="checkbox"/> Paper Tyvek
<input type="checkbox"/> Industrial Grade Safety Boots	<input type="checkbox"/> Other*	<input type="checkbox"/> NOT Required	<input type="checkbox"/> Hazard Category 2	<input type="checkbox"/> P95		<input type="checkbox"/> Polyethylene Tyvek
<input type="checkbox"/> Rubber Boots (industrial grade)		<input type="checkbox"/> Required	<input type="checkbox"/> Hazard Category 4	<input type="checkbox"/> R95		<input type="checkbox"/> Other*
<input type="checkbox"/> Hip Waders				<input type="checkbox"/> Organic Vapour		
	* see key equipment			<input type="checkbox"/> Speciality/Other*		

Project Development Team		Modified by		Reviewed by	Date
Name	Signature				
David Steele					

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
1	Discuss STAR and SWA	<ul style="list-style-type: none"> Site personnel not aware of STAR and SWA 	<ul style="list-style-type: none"> Project team (CRA) discusses importance of and documentation procedures for SWA during pre job safety meeting Discuss route, concerns, and alternate routes with passenger and drivers of other vehicles Use SWA to stop any work that is unsafe Ensure proper vehicle selected for travel (use a truck if going to construction site or area with rough conditions that would damage a small vehicle?) 	Driver and passenger
2	Check weather	<ul style="list-style-type: none"> Unexpected storm Fog; rain; snow; lightning/thunder Heat/cold stress 	<ul style="list-style-type: none"> Check local weather forecast Discuss weather issues and precautions to take while driving and on site during the pre job safety meeting If weather conditions (e.g., fog, rain, snow, etc.) impair the ability/vision of the driver, exit at nearest safe location and assess the situation While on site, at first sign of lightning/thunder utilize SWA and assess weather conditions In extreme temperatures, ensure all personnel have proper clothing, hydration, and heat/cold protection (e.g., canopy, fan, glove warmers) 	Driver or Passenger
3	Complete CRA Daily Operator Vehicle Checklist	<ul style="list-style-type: none"> Damaged vehicle lights, tires, windows, mirrors, horn Inadequate vehicle documents and/or safety items 	<ul style="list-style-type: none"> Check for fluid leaks under vehicle Test operation of headlights, front/rear turn signals, backup lights, brake lights, and emergency flashers Visually check the pressure/wear of tires Ensure the vehicle has a properly inflated spare tire and associated tools to install Assure windshield and window glass is clean and free from obstructions Assure all fluids are topped off (e.g., windshield wiper fluid) and scheduled routine maintenance has occurred (e.g., oil changes). Test the windshield wipers and horn Verify vehicle registration, insurance card, and inspection sticker is present and valid If the vehicle contains a first aid kit, fire extinguisher, and road hazard kit, verify that all items with expiration dates are current and that fire extinguisher has had documented monthly check Do not use vehicle if any safety device is found not functioning 	Driver or Passenger

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
4	Check and adjust seat, steering wheel, headrest, and mirrors	<ul style="list-style-type: none"> • Back/body strain • Blind spot • Impaired vision 	<p>Adjust seat, headrest, and steering wheel height so body is fully supported/comfortable and pedals are within easy reach</p> <p>Ensure mirrors are properly adjusted</p>	Driver or Passenger
5	Fasten seat belt(s) and ensure passengers' seat belts are fastened	<ul style="list-style-type: none"> • Serious injury, ejection, or death from collision and/or traffic citation 	<ul style="list-style-type: none"> • Verify driver and passenger(s) seat belts are in good condition and properly latched 	Driver or Passenger
6	Ensure vehicle doors are locked	<ul style="list-style-type: none"> • Serious injury, ejection, or death from collision • Unwanted intrusion • Lost equipment 	<ul style="list-style-type: none"> • Manually lock all doors to vehicle prior to starting the vehicle 	Driver
7	Start engine and check gauges and warning lights	<ul style="list-style-type: none"> • Vehicle breakdown 	<ul style="list-style-type: none"> • Verify sufficient fuel and other hazard lamps (e.g., battery, oil, and temperature) are not lit 	Driver
8	Driving – Use defensive driving techniques and stay alert	<ul style="list-style-type: none"> • Arriving late • Collision • Blind spots of other vehicles • Injury or death to occupants or other parties 	<ul style="list-style-type: none"> • Acknowledge and comply with all traffic regulations, laws, and ordinances • Do not use two way communicating devices or perform other distracting activities while vehicle is in motion • Constantly scan intersections, move eyes, check mirrors, and assess traffic lights (fresh vs. stale) • Recognize other vehicle's blind spots and minimize time spent within these zones • Maintain safety cushion around vehicle (front, sides, and rear) and 4 second following distance (add an extra second for each hazardous condition, triple following distance in poor weather conditions) • Signal well in advance before changing lanes or turning • Utilize all driving defensive techniques 	Driver
9	Arrive at site	<ul style="list-style-type: none"> • Pedestrian injury • Collision 	<ul style="list-style-type: none"> • Maintain awareness of pedestrian/vehicular traffic when entering site and traveling to work zone 	Driver
10	Park vehicle – assign a spotter if necessary (when in doubt use a spotter)	<ul style="list-style-type: none"> • Pedestrian injury • Collision • Property damage 	<ul style="list-style-type: none"> • Maintain awareness of pedestrian/vehicular traffic • Park vehicle in pull through parking space or facing the exit • Parking in a parking space that is not a designated parking space will require the placement of the 360 degree topper on the hood of the vehicle • Use caution and mirrors/spotter when backing vehicle • Set parking brake 	Driver

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
11	Demobilization – conduct a vehicle walk around inspection paying particular attention to path(s) of travel	<ul style="list-style-type: none"> • Collision • Injury or death to occupants or other parties 	<ul style="list-style-type: none"> • Perform perimeter vehicle check • Maintain awareness of pedestrian/vehicular traffic when exiting site • Utilize defensive driving techniques • Complete post departure checklist and report vehicle problems to company vehicle maintenance manager or rental car agency 	Driver or Passenger
12	Report maintenance or mechanical problems upon returning vehicle	<ul style="list-style-type: none"> • Conditions worsen leading to mechanical failure resulting in collision and injury 	<ul style="list-style-type: none"> • Report vehicle problems immediately to company representative or rental car agency • Schedule and/or perform repairs as soon as possible 	Driver

1. Each Job or Task consists of a set of steps. Be sure to list all the steps in the sequence that they are performed. Specify the equipment or other details to set the basis for the potential (associated) hazards.
2. A hazard is a potential danger. What can go wrong? How can someone get hurt? Consider, but do not limit, the analysis to: **Contact** - victim is struck by or strikes an object; **Caught** - victim is caught on, caught in or caught between objects; **Fall** - victim falls to ground or lower level (includes slips and trips); **Exertion** - excessive strain or stress/ergonomics/lifting techniques; **Exposure** - inhalation/skin hazards. Specify the hazards and do not limit the description to a single word such as "Caught".
3. Aligning with the Job Steps, Task Activity Description, and Potential Hazard columns, describe what actions or procedures are necessary to eliminate or minimize the hazards. Be clear, concise and specific. Use objective, observable, and quantified terms. Avoid subjective general statements such as "be careful" or "use as appropriate".

Site Personnel Participating in JSA Review:

I have participated in the review and discussion of the Job Safety Analysis (JSA) listed on this document and understand the duties I am responsible to fulfill. As part of my work, I know I have the responsibility and obligation to STOP work with a Stop Work Authority (SWA) if conditions change and/or potential hazards have been identified.

Name/Company	Sign	Date



SSE(s) on job: _____

Assigned mentor: _____

Presenter Signature: _____

Date/Time: _____

My signature below indicates that all conditions and requirements listed above have been verified, met, and reviewed with all affected personnel prior to start of work.

Supervisor Signature: _____

Date/Time: _____

Location of Mustering Point: _____

Wind direction (current): _____

GHD Emergency contact (Name and verified phone number): _____

Supervisor Signature documenting Daily Debrief has been completed: _____



Job Safety Analysis (JSA)

Insert Name: Environmental-Site Recon and Walkthrough

Field staff must review job specific work plan and coordinate with project manager to verify that all up front logistics are completed prior to starting work including, but not limited to, permitting, access agreements, and notification to required contacts (e.g., site managers, inspectors, clients, subcontractors, etc.). Additionally, a tailgate safety meeting must be performed and documented at the beginning of each workday. **Stop, Think, Act, Review (STAR)** must be used prior to any activity. All personnel must possess the appropriate training prior to initiating scheduled tasks. Also consider weather conditions. GHD personnel have the authority and responsibility to use **Stop Work Authority (SWA)**.

Date Issued/Revised:	3/21/2016 1:43:52 PM	Client:	Evergreen Resources Management		
Project Number:	11109626	Created By:	cra\dpsteele	SIM OPS? YES/NO	SSE on site? YES/NO
Project Address:	3144 West Passyunk Avenue Philadelphia				
Key Equipment:	<p>Basic PPE, hand/power tools based on site condition, site inspection checklist or notebook, JSA forms, pens, flashlight.</p> <p>Additional PPE: Insect repellent. Coveralls may be necessary based on type of brush/plants/insects in work area(s) being inspected. Leather gloves if overgrown vegetation or rundown buildings.</p>				
Task-specific Training:	SMART Safety training (STAR), JSA development, Poison Plant Identification				

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Type I (Top Impact)	<input type="checkbox"/> Chemical Protective (ie. Nitrile)	<input checked="" type="checkbox"/> ANSI/CSA Safety Glasses	<input type="checkbox"/> Harness	<input type="checkbox"/> Full Face Mask	<input checked="" type="checkbox"/> Class II	<input type="checkbox"/> Coveralls
<input type="checkbox"/> Type II (Side Impact)	<input checked="" type="checkbox"/> Level 1 Light Duty	<input type="checkbox"/> Goggles/Spoggles	<input type="checkbox"/> Shock Absorb Lanyard	<input type="checkbox"/> Half Face Mask	<input type="checkbox"/> Class III	<input type="checkbox"/> Fire Retardant Clothing (FRC)
<input checked="" type="checkbox"/> Class E (standard)	<input type="checkbox"/> Level 2 Light Duty with Protection	<input type="checkbox"/> Face Shield	<input type="checkbox"/> Lifeline		<input type="checkbox"/> Anti-Static	<input type="checkbox"/> High Viz Clothing
<input type="checkbox"/> Class G	<input type="checkbox"/> Level 3 Medium Duty	<input type="checkbox"/> Other*		Cartridges	<input type="checkbox"/> FRC	<input type="checkbox"/> Long Pants
	<input type="checkbox"/> Level 4 Heavy Duty			<input type="checkbox"/> N95	<input type="checkbox"/> PFD	<input type="checkbox"/> Long Sleeve Shirts
Foot Protection	<input type="checkbox"/> High Viz	Hearing Protection	Arc Flash/Shock Protection	<input type="checkbox"/> P100		<input type="checkbox"/> Paper Tyvek
<input checked="" type="checkbox"/> Industrial Grade Safety Boots	<input type="checkbox"/> Other*	<input checked="" type="checkbox"/> NOT Required	<input type="checkbox"/> Hazard Category 2	<input type="checkbox"/> P95		<input type="checkbox"/> Polyethylene Tyvek
<input type="checkbox"/> Rubber Boots (industrial grade)		<input type="checkbox"/> Required	<input type="checkbox"/> Hazard Category 4	<input type="checkbox"/> R95		<input type="checkbox"/> Other*

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Hip Waders				<input type="checkbox"/> Organic Vapour		
	* see key equipment			<input type="checkbox"/> Speciality/Other*		

Project Development Team		Modified by	Reviewed by	Date
Name	Signature			
David Steele				

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
1	Discuss STAR and SWA	<ul style="list-style-type: none"> Site personnel not aware of STAR and SWA 	<ul style="list-style-type: none"> Project team (CRA) discusses importance of and documentation procedures for SWA during pre job safety meeting Use SWA to stop any work that is unsafe 	All persons on project team
2	Check weather	<ul style="list-style-type: none"> Unexpected storm, fog; rain; snow; lightening, thunder Heat/cold stress 	<ul style="list-style-type: none"> Check local weather forecast Discuss weather issues and precautions to take while driving and on site during the pre job safety meeting If weather conditions (e.g., fog, rain, snow) impair the ability/vision of the driver, exit at nearest safe location and assess the situation While on site, at first sign of lightning/thunder utilize SWA and assess weather conditions In extreme temperatures, ensure all personnel have proper clothing, hydration, and heat/cold protection (e.g., canopy, fan, glove warmers) 	Assessor
3	Sign in	<ul style="list-style-type: none"> Site Manager and Operator not aware of CRA staff presence in facility or on grounds 	<ul style="list-style-type: none"> Sign in at front desk Ask to speak to Site Manager or alternate designate 	Assessor
4	Don necessary CRA and client required PPE	<ul style="list-style-type: none"> Contact with recyclable material or equipment 	<ul style="list-style-type: none"> Wear all required PPE (hard hat, vest, boots, and glasses) at all times while in the facility 	Assessor
5	Unload equipment from vehicle	<ul style="list-style-type: none"> Lifting hazards Back injury Manual material handling Cuts Pinch points Hand/foot injury Forgotten equipment Damaged equipment 	<ul style="list-style-type: none"> Reduce travel distance when there is a need to carry/lift materials Make sure grip is adequate; wear leather/cotton gloves Size up the load; if the object is too large or odd shaped OR is in excess of 50 pounds (23 kg) then assistance (mechanical or a buddy lift) will be required Lift with the legs (bend at the knees and use the leg muscles) to protect the lower back and keep lower back in a neutral position Avoid one handed carrying if possible; maintain awareness of footing Wear leather/cotton gloves and avoid placing hands/fingers in pinch point locations Wear steel toed boots Verify requested equipment against warehouse form Load equipment in an organized manner to prevent shifting during transport or use cargo netting 	Assessor

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
6	Complete site inspection and walkover of the property and work areas – Note any hazards that will impact site personnel and/or their operations	<ul style="list-style-type: none"> • Slip/trip/fall hazards • Insects/reptiles • Pedestrian injury • Poison plants 	<ul style="list-style-type: none"> • Check in with site personnel and sign appropriate visitor or safety log (may require watching safety video [i.e., plant]) • Check with site contact to determine safely accessible areas and areas where PPE are required • Wear PPE as directed by site personnel or dependent upon your evaluation of conditions • If building(s) looks dilapidated or in poor condition, do not enter • Watch for vehicles or other mobile equipment moving around • Make sure areas are well lit and you are accompanied by a site representative (if applicable) • Watch where you step on pavement (potholes, dips, or obstructions) and in vegetated/wooded areas (dips, holes, branches, vines, etc.) • Do not take photographs while walking • Do not talk on cell phone while walking • If in vegetated or wooded areas, watch for beehives, wear insect repellent (if area and season dictate) as needed, be mindful of gopher holes/tunnels, small animal dens, snakes, stray dogs/cats, transient/homeless individuals, poison ivy/oak/sumac, etc. 	Assessor
7	Sign out	<ul style="list-style-type: none"> • Site Manager and Operator not aware that CRA staff have left facility 	<ul style="list-style-type: none"> • Sign out at front desk • Ask to speak to Site Manager or alternate designate 	Assessor
8	Demobilization	<ul style="list-style-type: none"> • Collision • Injury or death to vehicle occupants or other parties 	<ul style="list-style-type: none"> • Perform perimeter vehicle check • Maintain awareness of pedestrian/vehicular traffic when exiting the site • Utilize defensive driving techniques • Complete post departure checklist and report vehicle problems to company vehicle maintenance manager or rental car agency 	Assessor

1. Each Job or Task consists of a set of steps. Be sure to list all the steps in the sequence that they are performed. Specify the equipment or other details to set the basis for the potential (associated) hazards.
2. A hazard is a potential danger. What can go wrong? How can someone get hurt? Consider, but do not limit, the analysis to: **Contact** - victim is struck by or strikes an object; **Caught** - victim is caught on, caught in or caught between objects; **Fall** - victim falls to ground or lower level (includes slips and trips); **Exertion** - excessive strain or stress/ergonomics/lifting techniques; **Exposure** - inhalation/skin hazards. Specify the hazards and do not limit the description to a single word such as "Caught".
3. Aligning with the Job Steps, Task Activity Description, and Potential Hazard columns, describe what actions or procedures are necessary to eliminate or minimize the hazards. Be clear, concise and specific. Use objective, observable, and quantified terms. Avoid subjective general statements such as "be careful" or "use as appropriate".

Site Personnel Participating in JSA Review:

I have participated in the review and discussion of the Job Safety Analysis (JSA) listed on this document and understand the duties I am responsible to fulfill. As part of my work, I know I have the responsibility and obligation to STOP work with a Stop Work Authority (SWA) if conditions change and/or potential hazards have been identified.

Name/Company	Sign	Date



SSE(s) on job: _____

Assigned mentor: _____

Presenter Signature: _____

Date/Time: _____

My signature below indicates that all conditions and requirements listed above have been verified, met, and reviewed with all affected personnel prior to start of work.

Supervisor Signature: _____

Date/Time: _____

Location of Mustering Point: _____

Wind direction (current): _____

GHD Emergency contact (Name and verified phone number): _____

Supervisor Signature documenting Daily Debrief has been completed: _____



Job Safety Analysis (JSA)

Insert Name: Environmental-Oversight of
Monitoring Well Installation
and/or Soil Boring

Field staff must review job specific work plan and coordinate with project manager to verify that all up front logistics are completed prior to starting work including, but not limited to, permitting, access agreements, and notification to required contacts (e.g., site managers, inspectors, clients, subcontractors, etc.). Additionally, a tailgate safety meeting must be performed and documented at the beginning of each workday. **Stop, Think, Act, Review (STAR)** must be used prior to any activity. All personnel must possess the appropriate training prior to initiating scheduled tasks. Also consider weather conditions. GHD personnel have the authority and responsibility to use **Stop Work Authority (SWA)**.

Date Issued/Revised:	3/21/2016 1:43:51 PM	Client:	Evergreen Resources Management		
Project Number:	11109626	Created By:	cra/dpstele	SIM OPS? YES/NO	SSE on site? YES/NO
Project Address:	3144 West Passyunk Avenue Philadelphia				
Key Equipment:	Air monitoring equipment; safety cones/fencing/barricades (not needed in vacant, fenced areas)				
Task-specific Training:					

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Type I (Top Impact)	<input type="checkbox"/> Chemical Protective (ie. Nitrile)	<input checked="" type="checkbox"/> ANSI/CSA Safety Glasses	<input type="checkbox"/> Harness	<input type="checkbox"/> Full Face Mask	<input checked="" type="checkbox"/> Class II	<input type="checkbox"/> Coveralls
<input type="checkbox"/> Type II (Side Impact)	<input checked="" type="checkbox"/> Level 1 Light Duty	<input type="checkbox"/> Goggles/Spoggles	<input type="checkbox"/> Shock Absorb Lanyard	<input type="checkbox"/> Half Face Mask	<input type="checkbox"/> Class III	<input type="checkbox"/> Fire Retardant Clothing (FRC)
<input checked="" type="checkbox"/> Class E (standard)	<input type="checkbox"/> Level 2 Light Duty with Protection	<input type="checkbox"/> Face Shield	<input type="checkbox"/> Lifeline		<input type="checkbox"/> Anti- Static	<input type="checkbox"/> High Viz Clothing
<input type="checkbox"/> Class G	<input type="checkbox"/> Level 3 Medium Duty	<input type="checkbox"/> Other*		Cartridges	<input type="checkbox"/> FRC	<input type="checkbox"/> Long Pants
	<input type="checkbox"/> Level 4 Heavy Duty			<input type="checkbox"/> N95	<input type="checkbox"/> PFD	<input type="checkbox"/> Long Sleeve Shirts
Foot Protection	<input type="checkbox"/> High Viz	Hearing Protection	Arc Flash/Shock Protection	<input type="checkbox"/> P100		<input type="checkbox"/> Paper Tyvek
<input checked="" type="checkbox"/> Industrial Grade Safety Boots	<input type="checkbox"/> Other*	<input type="checkbox"/> NOT Required	<input type="checkbox"/> Hazard Category 2	<input type="checkbox"/> P95		<input type="checkbox"/> Polyethylene Tyvek
<input type="checkbox"/> Rubber Boots (industrial grade)		<input checked="" type="checkbox"/> Required	<input type="checkbox"/> Hazard Category 4	<input type="checkbox"/> R95		<input type="checkbox"/> Other*
<input type="checkbox"/> Hip Waders				<input type="checkbox"/> Organic Vapour		

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
	* see key equipment			<input type="checkbox"/> Speciality/Other*		

Project Development Team		Modified by	Reviewed by	Date
Name	Signature			
David Steele				

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
1	Markout underground utilities	<ul style="list-style-type: none"> • Property damage • Explosion • Electrocution • Injury • Death 	<ul style="list-style-type: none"> • Call public underground utility agency (One Call) at least 5 or more days prior to work activities • Review State Law pertaining to underground pipe line safety and have private utility mark out performed • Expose lines if warranted (i.e., hand dig, test pit, or daylight) 	Project Manager and Site Supervisor
2	Conduct site walk, identify unsafe conditions and determine sample point locations	<ul style="list-style-type: none"> • Traffic hazard • Slip/trip/fall hazards • Biological hazard • Overhead/underground hazards 	<ul style="list-style-type: none"> • Maintain awareness of on site traffic and walking surfaces • When selecting soil boring locations, be aware of biological hazards (e.g., ants, poison ivy, wasps) and overhead/underground hazards (e.g., overhead utilities, concrete scarring, station canopy) 	Site Personnel
3	Equipment inspection	<ul style="list-style-type: none"> • Pinch points • Property damage • Lost time due to damaged equipment/parts 	<ul style="list-style-type: none"> • Discuss pinch points on equipment (e.g., drill rig, air knife, pressure washer, etc.) • Familiarize all personnel with location/operation of fire extinguisher(s) and kill switch on drill rig • Visually inspect equipment/parts for damage and document inspections 	Site Personnel
4	Set up work zone for drilling	<ul style="list-style-type: none"> • Traffic hazard • Slip/trip/fall hazards • Property damage • Overhead hazards • Environmental impact • Unstable ground conditions 	<ul style="list-style-type: none"> • Maintain awareness of on site traffic, work zones, walking surfaces, overhead hazards (e.g., canopy and low hanging overhead lines) • Utilize barricades/cones/caution tape to define work zone and direct traffic • Wear leather/cotton when setting up barricades • Be aware of any potential sensitive receptors and verify all personnel are aware of the location of spill kit • Inspect soil for loose, soft or unstable conditions under rig jacks or outriggers 	Site Personnel

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
5	Set up staging area	<ul style="list-style-type: none"> • Traffic hazard • Slip/trip/fall hazards • Lifting hazards • Back injury • Manual material handling • Pinch points • Heat/cold stress 	<ul style="list-style-type: none"> • Maintain awareness of on site traffic and walking surfaces • Utilize barricades/cones/caution tape to define work zone and direct traffic • Reduce distance needed to travel when carrying materials and or equipment • Wear leather/cotton gloves when setting up barricades • Size up the load, If the object is too large or odd shaped OR is in excess of 50 pounds (23 kg) then assistance (mechanical or a buddy lift) will be required. • Lift with the legs (bend at the knees and use the leg muscles) to protect the lower back and keep lower back in a neutral position • Avoid one handed carrying if possible; maintain awareness of footing • Avoid placing hands/fingers in pinch point locations • In extreme temperatures, ensure all personnel have proper clothing, hydration, and heat/cold protection (e.g., canopy, fan, glove warmers) 	Site Personnel
6	Contractor oversight/ management of hole clearance/drilling activities	<ul style="list-style-type: none"> • Traffic hazard • Slip/trip/fall hazards • Lifting hazards • Back injury • Manual material handling • Damage to underground utilities • Contaminant exposure • Heat/cold stress • Injury to personnel and public • Cross contamination • Equipment failure 	<ul style="list-style-type: none"> • Maintain awareness of on site traffic and practice good housekeeping • Perform a prestart meeting, inform subcontractor of safe lifting practices • Refer to step 5 and the HASP for additional lifting information • Ensure subcontractors don proper PPE (e.g., face shield, leather/cotton gloves, hearing protection). No loose clothing. • Complete and sign off utility clearance. If non native material (e.g., pea gravel, sand, fill material) or underground utilities are observed, utilize SWA and assess situation. • Monitor breathing zone and refer to HASP for action levels • Monitor all personnel for signs and symptoms of heat/cold stress and refer to HASP for recommendations • Be aware of unsafe hoisting and material handling practices • Be aware of proper augering and auger handling techniques. Visually monitor performance and functioning of drill rig for signs of failure. Monitor safe drill movement/positional setup. • Decontaminate sampling equipment after collecting a sample and decontaminate drilling equipment after each borehole • Watch where you step, look for debris which may be covered by brush or rubble 	Site Personnel

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
7	Construct well	<ul style="list-style-type: none"> • Lifting hazards • Back injury • Manual material handling • Cross contamination • Non approved construction • Slip, trip, and fall hazards • Eye injury • Cuts 	<ul style="list-style-type: none"> • Use proper lifting techniques as discussed in Step 5 and HASP • Prior to going into the borehole, inspect casing and other materials to ensure they are free of jagged/sharp edges • Confirm construction with project manager • Ensure presence or other authorization by any required inspectors for well installation/grouting • Keep pathways and work area clean of debris and possible tripping hazards • Use PPE and monitoring in accordance with the JSA • Use safe cutting tools (no fixed open blade knives) 	
8	Site/boring security, clean site, demobilize	<ul style="list-style-type: none"> • Traffic hazard • Slip/trip/fall hazards • Lifting hazards • Back safety • Manual material handling 	<ul style="list-style-type: none"> • Use buddy system as necessary to remove traffic control • Do not work with your back to traffic • Wear leather/cotton gloves when moving barricades • Maintain awareness of on site traffic and walking surfaces • Maintain proper lifting techniques as described in Step 5 and HASP. • Ensure good house keeping methods are practiced. Work area is kept clean of debris. • Leave site clean of refuse and debris • Clearly mark/barricade any borings that need later topping off or curing • Notify property personnel of departure • Secure boring location if open overnight 	

1. Each Job or Task consists of a set of steps. Be sure to list all the steps in the sequence that they are performed. Specify the equipment or other details to set the basis for the potential (associated) hazards.
2. A hazard is a potential danger. What can go wrong? How can someone get hurt? Consider, but do not limit, the analysis to: **Contact** - victim is struck by or strikes an object; **Caught** - victim is caught on, caught in or caught between objects; **Fall** - victim falls to ground or lower level (includes slips and trips); **Exertion** - excessive strain or stress/ergonomics/lifting techniques; **Exposure** - inhalation/skin hazards. Specify the hazards and do not limit the description to a single word such as "Caught".
3. Aligning with the Job Steps, Task Activity Description, and Potential Hazard columns, describe what actions or procedures are necessary to eliminate or minimize the hazards. Be clear, concise and specific. Use objective, observable, and quantified terms. Avoid subjective general statements such as "be careful" or "use as appropriate".

Site Personnel Participating in JSA Review:

I have participated in the review and discussion of the Job Safety Analysis (JSA) listed on this document and understand the duties I am responsible to fulfill. As part of my work, I know I have the responsibility and obligation to STOP work with a Stop Work Authority (SWA) if conditions change and/or potential hazards have been identified.

Name/Company	Sign	Date



SSE(s) on job: _____

Assigned mentor: _____

Presenter Signature: _____

Date/Time: _____

My signature below indicates that all conditions and requirements listed above have been verified, met, and reviewed with all affected personnel prior to start of work.

Supervisor Signature: _____

Date/Time: _____

Location of Mustering Point: _____

Wind direction (current): _____

GHD Emergency contact (Name and verified phone number): _____

Supervisor Signature documenting Daily Debrief has been completed: _____



Job Safety Analysis (JSA)

Insert Name: Environmental-Soil Sampling

Field staff must review job specific work plan and coordinate with project manager to verify that all up front logistics are completed prior to starting work including, but not limited to, permitting, access agreements, and notification to required contacts (e.g., site managers, inspectors, clients, subcontractors, etc.). Additionally, a tailgate safety meeting must be performed and documented at the beginning of each workday. **Stop, Think, Act, Review (STAR)** must be used prior to any activity. All personnel must possess the appropriate training prior to initiating scheduled tasks. Also consider weather conditions. GHD personnel have the authority and responsibility to use **Stop Work Authority (SWA)**.

Date Issued/Revised:	2/11/2016 6:22:21 PM	Client:	Evergreen Resources Management		
Project Number:	11109626	Created By:	cra\MMarcus	SIM OPS? YES/NO	SSE on site? YES/NO
Project Address:	3144 West Passyunk Avenue Philadelphia				
Key Equipment:	Air monitoring equipment, PPE Additional PPE: Tyvek if Level C initiated; gloves dependent on the task and chemical contamination present or suspected present				
Task-specific Training:	CRA Field Method Training on Soil Sampling Procedures				

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Type I (Top Impact)	<input type="checkbox"/> Chemical Protective (ie. Nitrile)	<input checked="" type="checkbox"/> ANSI/CSA Safety Glasses	<input type="checkbox"/> Harness	<input type="checkbox"/> Full Face Mask	<input checked="" type="checkbox"/> Class II	<input type="checkbox"/> Coveralls
<input type="checkbox"/> Type II (Side Impact)	<input checked="" type="checkbox"/> Level 1 Light Duty	<input type="checkbox"/> Goggles/Spoggles	<input type="checkbox"/> Shock Absorb Lanyard	<input type="checkbox"/> Half Face Mask	<input type="checkbox"/> Class III	<input type="checkbox"/> Fire Retardant Clothing (FRC)
<input checked="" type="checkbox"/> Class E (standard)	<input type="checkbox"/> Level 2 Light Duty with Protection	<input type="checkbox"/> Face Shield	<input type="checkbox"/> Lifeline		<input type="checkbox"/> Anti-Static	<input type="checkbox"/> High Viz Clothing
<input type="checkbox"/> Class G	<input type="checkbox"/> Level 3 Medium Duty	<input type="checkbox"/> Other*		Cartridges	<input type="checkbox"/> FRC	<input type="checkbox"/> Long Pants
	<input type="checkbox"/> Level 4 Heavy Duty			<input type="checkbox"/> N95	<input type="checkbox"/> PFD	<input type="checkbox"/> Long Sleeve Shirts
Foot Protection	<input type="checkbox"/> High Viz	Hearing Protection	Arc Flash/Shock Protection	<input type="checkbox"/> P100		<input type="checkbox"/> Paper Tyvek
<input checked="" type="checkbox"/> Industrial Grade Safety Boots	<input type="checkbox"/> Other*	<input checked="" type="checkbox"/> NOT Required	<input type="checkbox"/> Hazard Category 2	<input type="checkbox"/> P95		<input type="checkbox"/> Polyethylene Tyvek
<input type="checkbox"/> Rubber Boots (industrial grade)		<input type="checkbox"/> Required	<input type="checkbox"/> Hazard Category 4	<input type="checkbox"/> R95		<input type="checkbox"/> Other*
<input type="checkbox"/> Hip Waders				<input type="checkbox"/> Organic Vapour		

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
	* see key equipment			<input type="checkbox"/> Speciality/Other*		

Project Development Team		Modified by	Reviewed by	Date
Name	Signature			
David Steele				

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
1	Discuss STAR and SWA	<ul style="list-style-type: none"> Site personnel not aware of STAR and SWA 	<ul style="list-style-type: none"> Project team (CRA) discusses importance of and documentation procedures for SWA during pre job safety meeting Use SWA to stop any work that is unsafe 	Site Personnel
2	Inspect and calibrate sampling and monitoring equipment	<ul style="list-style-type: none"> Lost time from improperly functioning equipment Incorrect sampling procedures/ collection due to malfunctioning equipment 	<ul style="list-style-type: none"> Ensure all equipment is functioning properly Complete Quality Control documents 	Sampling Technician
3	Prepare to collect soil samples	<ul style="list-style-type: none"> Lifting hazards Back injury Manual material handling Pinch points Cuts Punctures Sample misidentification 	<ul style="list-style-type: none"> Size up the load; if the object is too large or odd shaped OR is in excess of 50 pounds (23 kg) then assistance (mechanical or a buddy lift) will be required Lift with the legs (bend at the knees and use the leg muscles) to protect the lower back and keep lower back in a neutral position Avoid one handed carrying if possible; maintain awareness of footing No bending or twisting while under load Refer to the HASP for additional lifting information Avoid placing hands/fingers in pinch point locations Use proper tools when opening container packaging Do not use fixed open blade knives when opening boxes or containers Ensure the sample id label matches sample location with site plan/CRA site supervisor/subcontractor 	Sampling Technician
4	Opening the sample sleeve (if applicable)	<ul style="list-style-type: none"> Cuts due to sharp edges of sample sleeve Contaminant exposure 	<ul style="list-style-type: none"> Use sleeve cutter for opening the sample sleeves Keep hands clear of the sleeve when cutting Wear nitrile gloves Maintain awareness of sharp edges of sample sleeve 	Sampling Technician
5	Sample collection	<ul style="list-style-type: none"> Contaminant exposure Cuts from container breakage Sample misidentification 	<ul style="list-style-type: none"> Wear nitrile gloves and replace between soil samples Inspect glass bottles for breaks/cracks Do not attempt to use any suspect containers Close glass sample containers carefully to avoid breakage Check sample labels for accuracy prior to placing in cooler 	Sampling Technician
6	Headspace screening of samples	<ul style="list-style-type: none"> Contaminant exposure Incorrect headspace readings 	<ul style="list-style-type: none"> Wear nitrile gloves Ensure proper calibration of equipment 	Sampling Technician
7	Sample selection	<ul style="list-style-type: none"> Bottle breakage Contaminant exposure Pinch points Lost time due to incorrect sample selection 	<ul style="list-style-type: none"> Wear nitrile gloves when handling sample containers Confirm selected samples are correct based on work plan selection criteria, PID readings, and soil boring logs Avoid placing hands/fingers in pinch point locations (e.g., between cooler and lid) 	Sampling Technician

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
8	Packing samples in cooler(s)	<ul style="list-style-type: none"> ● Bottle breakage ● Contaminant exposure ● Cuts ● Pinch points ● Lifting hazards ● Back injury ● Manual material handling ● Lost time due to incorrect sample packaging or hold time exceedances 	<ul style="list-style-type: none"> ● Wear nitrile gloves when handling sample containers ● Pack glass containers in bubble wrap ● Check COC against sample labels and SSOW for accuracy before shipping ● Avoid placing hands/fingers in pinch point locations (e.g., between cooler and lid) ● Use proper lifting techniques as discussed in step 3 ● If possible use a dolly or cart if cooler is heavy or has to be moved over a long distance ● Ensure equipment and supplies are loaded correctly and do not shift during transport 	Sampling Technician
9	Investigation derived waste (IDW) management	<ul style="list-style-type: none"> ● Contaminant exposure ● Lifting hazards ● Back injury ● Manual material handling ● Pinch points ● Slips/trips/fall hazards ● Mislabeled waste 	<ul style="list-style-type: none"> ● Wear nitrile gloves when handling IDW ● Use proper lifting techniques as discussed in step 3 ● Avoid placing hands/fingers in pinch point locations ● Maintain awareness of walking surfaces ● Label IDW with generator, a contact number, identification of contents, and site location ● Specify IDW as either hazardous or non hazardous material 	Sampling Technician

1. Each Job or Task consists of a set of steps. Be sure to list all the steps in the sequence that they are performed. Specify the equipment or other details to set the basis for the potential (associated) hazards.
2. A hazard is a potential danger. What can go wrong? How can someone get hurt? Consider, but do not limit, the analysis to: **Contact** - victim is struck by or strikes an object; **Caught** - victim is caught on, caught in or caught between objects; **Fall** - victim falls to ground or lower level (includes slips and trips); **Exertion** - excessive strain or stress/ergonomics/lifting techniques; **Exposure** - inhalation/skin hazards. Specify the hazards and do not limit the description to a single word such as "Caught".
3. Aligning with the Job Steps, Task Activity Description, and Potential Hazard columns, describe what actions or procedures are necessary to eliminate or minimize the hazards. Be clear, concise and specific. Use objective, observable, and quantified terms. Avoid subjective general statements such as "be careful" or "use as appropriate".

Site Personnel Participating in JSA Review:

I have participated in the review and discussion of the Job Safety Analysis (JSA) listed on this document and understand the duties I am responsible to fulfill. As part of my work, I know I have the responsibility and obligation to STOP work with a Stop Work Authority (SWA) if conditions change and/or potential hazards have been identified.

Name/Company	Sign	Date



SSE(s) on job: _____

Assigned mentor: _____

Presenter Signature: _____

Date/Time: _____

My signature below indicates that all conditions and requirements listed above have been verified, met, and reviewed with all affected personnel prior to start of work.

Supervisor Signature: _____

Date/Time: _____

Location of Mustering Point: _____

Wind direction (current): _____

GHD Emergency contact (Name and verified phone number): _____

Supervisor Signature documenting Daily Debrief has been completed: _____



Job Safety Analysis (JSA)

Insert Name: Environmental- Monitoring
Well Sampling

Field staff must review job specific work plan and coordinate with project manager to verify that all up front logistics are completed prior to starting work including, but not limited to, permitting, access agreements, and notification to required contacts (e.g., site managers, inspectors, clients, subcontractors, etc.). Additionally, a tailgate safety meeting must be performed and documented at the beginning of each workday. **Stop, Think, Act, Review (STAR)** must be used prior to any activity. All personnel must possess the appropriate training prior to initiating scheduled tasks. Also consider weather conditions. GHD personnel have the authority and responsibility to use **Stop Work Authority (SWA)**.

Date Issued/Revised:	2/11/2016 6:22:21 PM	Client:	Evergreen Resources Management		
Project Number:	11109626	Created By:	cra\MMarcus	SIM OPS? YES/NO	SSE on site? YES/NO
Project Address:	3144 West Passyunk Avenue Philadelphia				
Key Equipment:					
Task-specific Training:					

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Type I (Top Impact)	<input checked="" type="checkbox"/> Chemical Protective (ie. Nitrile)	<input type="checkbox"/> ANSI/CSA Safety Glasses	<input type="checkbox"/> Harness	<input type="checkbox"/> Full Face Mask	<input type="checkbox"/> Class II	<input type="checkbox"/> Coveralls
<input type="checkbox"/> Type II (Side Impact)	<input type="checkbox"/> Level 1 Light Duty	<input type="checkbox"/> Goggles/Spoggles	<input type="checkbox"/> Shock Absorb Lanyard	<input type="checkbox"/> Half Face Mask	<input type="checkbox"/> Class III	<input type="checkbox"/> Fire Retardant Clothing (FRC)
<input type="checkbox"/> Class E (standard)	<input type="checkbox"/> Level 2 Light Duty with Protection	<input type="checkbox"/> Face Shield	<input type="checkbox"/> Lifeline		<input type="checkbox"/> Anti-Static	<input type="checkbox"/> High Viz Clothing
<input type="checkbox"/> Class G	<input type="checkbox"/> Level 3 Medium Duty	<input type="checkbox"/> Other*		Cartridges	<input type="checkbox"/> FRC	<input type="checkbox"/> Long Pants
	<input type="checkbox"/> Level 4 Heavy Duty			<input type="checkbox"/> N95	<input type="checkbox"/> PFD	<input type="checkbox"/> Long Sleeve Shirts
Foot Protection	<input type="checkbox"/> High Viz	Hearing Protection	Arc Flash/Shock Protection	<input type="checkbox"/> P100		<input type="checkbox"/> Paper Tyvek
<input type="checkbox"/> Industrial Grade Safety Boots	<input type="checkbox"/> Other*	<input type="checkbox"/> NOT Required	<input type="checkbox"/> Hazard Category 2	<input type="checkbox"/> P95		<input type="checkbox"/> Polyethylene Tyvek
<input type="checkbox"/> Rubber Boots (industrial grade)		<input type="checkbox"/> Required	<input type="checkbox"/> Hazard Category 4	<input type="checkbox"/> R95		<input type="checkbox"/> Other*
<input type="checkbox"/> Hip Waders				<input type="checkbox"/> Organic Vapour		
	* see key equipment			<input type="checkbox"/> Speciality/Other*		

Project Development Team		Modified by	Reviewed by	Date
Name	Signature			
David Steele				

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
1	Coordinate site access	<ul style="list-style-type: none"> Delays or added work 	<ul style="list-style-type: none"> Notify Station Manager of schedule Notify other required personnel if applicable (city, regulators, private property owners, etc.) 	
2	Mobilize with proper equipment/ supplies for sampling	<ul style="list-style-type: none"> Delay or improper/unsafe performance of work due to improper equipment on site Cross contamination of wells 	<ul style="list-style-type: none"> Review work plan to determine equipment/supply needs Make sure all sampling/gauging equipment is decontaminated Bring ice for sample storage Review THE HASP and gather necessary PPE 	
3	Notify other personnel on site	<ul style="list-style-type: none"> Unknown traffic or other work hazards Lack of communication between all interested parties 	<ul style="list-style-type: none"> Meet with station attendant or other site personnel and explain planned activities 	
4	Determine sampling order	<ul style="list-style-type: none"> Cross contamination of samples and wells due to incomplete decontamination of sampling equipment 	<ul style="list-style-type: none"> Review prior analytical results and set sampling order from lowest to highest concentration wells 	
5	Perform STAR and tailgate safety meeting upon arrival at site	<ul style="list-style-type: none"> Consider worst case scenario (including weather conditions) 	<ul style="list-style-type: none"> Review HASP with co workers Highlight aspects identified by HASP and, if necessary, add to HASP Get signature of all co workers on HASP 	
6	Set up exclusion zone(s)	<ul style="list-style-type: none"> Injury or exposure to public or other on site personnel Slip/trip/fall hazards 	<ul style="list-style-type: none"> Implement exclusion zone setup instructions of THE HASP (barricades, caution tape, cones, etc.) Set up work area free of trip hazards 	
7	Gauge water levels and product thickness (where applicable) in wells	<ul style="list-style-type: none"> Back strain Inhalation or dermal exposure to chemical hazards 	<ul style="list-style-type: none"> Don any additional PPE and initiate air quality monitoring in accordance with the HASP Maintain safe distance from well head Bend at knees, not waist 	

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
8	Purge well(s) and collect purge water	<ul style="list-style-type: none"> • Cross contamination • Lifting hazards • Back injury • Manual material handling • Inhalation or dermal exposure to chemicals • Slip/trip/fall hazards • Spilling contaminated water 	<ul style="list-style-type: none"> • Decontaminate purging equipment between each sampling location • Reduce travel distance when there is a need to carry/lift materials • Make sure grip is adequate; wear leather/cotton gloves • Size up the load; if the object is too large or odd shaped OR is in excess of 50 pounds (23 kg) then assistance (mechanical or a buddy lift) will be required • Lift with the legs (bend at the knees and use the leg muscles) to protect the lower back and keep lower back in a neutral position • Avoid one handed carrying if possible; maintain awareness of footing • Use PPE and monitoring in accordance with the HASP • Keep work area clear of tripping or slipping hazards • Store purge water in appropriate containers 	
9	Collect samples in accordance with sampling plan	<ul style="list-style-type: none"> • Cross contamination • Lifting hazards • Back injury • Manual material handling • Inhalation or dermal exposure to chemical hazards • Slip/trip/fall hazards • Improper labeling or storage • Injury due to acid burn (unsealed or leaking sample bottle) • Injury from broken sample bottle (cuts or acid burn) 	<ul style="list-style-type: none"> • Use PPE in accordance with the HASP • Use PPE whenever handling or labeling samples • Decontaminate sampling equipment between each well (unless disposable) • Refer to step 9 and the HASP for additional lifting methods • Label samples in accordance with sampling plan • Keep samples stored in proper containers, at correct temperature, and away from work area • Wear nitrile gloves when handling bottles • Handle bottles carefully 	
10	Dispose or store purge water onsite	<ul style="list-style-type: none"> • Lifting hazards • Back injury • Manual material handling • Exposure to chemicals • If disposing through on site treatment system, damage or injury from improper use of equipment • Improper storage or disposal 	<ul style="list-style-type: none"> • Use proper equipment to transport water (pumps, drum dollies, etc.) • Refer to step 9 and the HASP for additional lifting methods • Where PPE in accordance with the HASP • Review any necessary instructions for use of on site treatment systems • Label storage containers properly and locate in isolated area away from traffic and other site functions • Coordinate off site disposal (where applicable) 	
11	Clean site/demobilize	<ul style="list-style-type: none"> • Traffic • Nuisance or safety hazard left on site • Back strain 	<ul style="list-style-type: none"> • Use buddy system as necessary to remove traffic control • Leave site clean of refuse and debris • Notify station personnel of departure, and note any purge water left on site • Exercise caution when lifting coolers out of the trunk of a car; use the buddy system if justified 	

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
12	Package and deliver samples to lab	<ul style="list-style-type: none"> • Bottle breakage • Improper temperature • Exceeding hold times • Improper completion of Chain of Custody (COC) 	<ul style="list-style-type: none"> • Pack samples in ice, use bubble wrap/bags for sample bottles • Use standard COC forms and labels • Submit samples to lab as soon as possible (no more than 3 days, but check sampling plan for any special requirements such as rush turnaround or special hold time restrictions) 	

1. Each Job or Task consists of a set of steps. Be sure to list all the steps in the sequence that they are performed. Specify the equipment or other details to set the basis for the potential (associated) hazards.
2. A hazard is a potential danger. What can go wrong? How can someone get hurt? Consider, but do not limit, the analysis to: **Contact** - victim is struck by or strikes an object; **Caught** - victim is caught on, caught in or caught between objects; **Fall** - victim falls to ground or lower level (includes slips and trips); **Exertion** - excessive strain or stress/ergonomics/lifting techniques; **Exposure** - inhalation/skin hazards. Specify the hazards and do not limit the description to a single word such as "Caught".
3. Aligning with the Job Steps, Task Activity Description, and Potential Hazard columns, describe what actions or procedures are necessary to eliminate or minimize the hazards. Be clear, concise and specific. Use objective, observable, and quantified terms. Avoid subjective general statements such as "be careful" or "use as appropriate".

Site Personnel Participating in JSA Review:

I have participated in the review and discussion of the Job Safety Analysis (JSA) listed on this document and understand the duties I am responsible to fulfill. As part of my work, I know I have the responsibility and obligation to STOP work with a Stop Work Authority (SWA) if conditions change and/or potential hazards have been identified.

Name/Company	Sign	Date



SSE(s) on job: _____

Assigned mentor: _____

Presenter Signature: _____

Date/Time: _____

My signature below indicates that all conditions and requirements listed above have been verified, met, and reviewed with all affected personnel prior to start of work.

Supervisor Signature: _____

Date/Time: _____

Location of Mustering Point: _____

Wind direction (current): _____

GHD Emergency contact (Name and verified phone number): _____

Supervisor Signature documenting Daily Debrief has been completed: _____



Job Safety Analysis (JSA)

Insert Name: Drilling-Monitoring Well Pad Construction

Field staff must review job specific work plan and coordinate with project manager to verify that all up front logistics are completed prior to starting work including, but not limited to, permitting, access agreements, and notification to required contacts (e.g., site managers, inspectors, clients, subcontractors, etc.). Additionally, a tailgate safety meeting must be performed and documented at the beginning of each workday. **Stop, Think, Act, Review (STAR)** must be used prior to any activity. All personnel must possess the appropriate training prior to initiating scheduled tasks. Also consider weather conditions. GHD personnel have the authority and responsibility to use **Stop Work Authority (SWA)**.

Date Issued/Revised:	3/21/2016 1:39:42 PM	Client:	Evergreen Resources Management		
Project Number:	11109626	Created By:	cra\dpsteele	SIM OPS? YES/NO	SSE on site? YES/NO
Project Address:	3144 West Passyunk Avenue Philadelphia				
Key Equipment:	Wheel barrow, shovel				
Task-specific Training:	Hand tool, hands on training				

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Type I (Top Impact)	<input type="checkbox"/> Chemical Protective (ie. Nitrile)	<input checked="" type="checkbox"/> ANSI/CSA Safety Glasses	<input type="checkbox"/> Harness	<input type="checkbox"/> Full Face Mask	<input checked="" type="checkbox"/> Class II	<input type="checkbox"/> Coveralls
<input type="checkbox"/> Type II (Side Impact)	<input checked="" type="checkbox"/> Level 1 Light Duty	<input type="checkbox"/> Goggles/Spoggles	<input type="checkbox"/> Shock Absorb Lanyard	<input type="checkbox"/> Half Face Mask	<input type="checkbox"/> Class III	<input type="checkbox"/> Fire Retardant Clothing (FRC)
<input checked="" type="checkbox"/> Class E (standard)	<input type="checkbox"/> Level 2 Light Duty with Protection	<input type="checkbox"/> Face Shield	<input type="checkbox"/> Lifeline		<input type="checkbox"/> Anti-Static	<input type="checkbox"/> High Viz Clothing
<input type="checkbox"/> Class G	<input type="checkbox"/> Level 3 Medium Duty	<input type="checkbox"/> Other*		Cartridges	<input type="checkbox"/> FRC	<input type="checkbox"/> Long Pants
	<input type="checkbox"/> Level 4 Heavy Duty			<input type="checkbox"/> N95	<input type="checkbox"/> PFD	<input type="checkbox"/> Long Sleeve Shirts
Foot Protection	<input type="checkbox"/> High Viz	Hearing Protection	Arc Flash/Shock Protection	<input type="checkbox"/> P100		<input type="checkbox"/> Paper Tyvek
<input checked="" type="checkbox"/> Industrial Grade Safety Boots	<input type="checkbox"/> Other*	<input checked="" type="checkbox"/> NOT Required	<input type="checkbox"/> Hazard Category 2	<input type="checkbox"/> P95		<input type="checkbox"/> Polyethylene Tyvek
<input type="checkbox"/> Rubber Boots (industrial grade)		<input type="checkbox"/> Required	<input type="checkbox"/> Hazard Category 4	<input type="checkbox"/> R95		<input type="checkbox"/> Other*
<input type="checkbox"/> Hip Waders				<input type="checkbox"/> Organic Vapour		

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
	* see key equipment			<input type="checkbox"/> Speciality/Other*		

Project Development Team		Modified by	Reviewed by	Date
Name	Signature			
David Steele				

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
1	Review STAR process and SWA policy	<ul style="list-style-type: none"> Personal injury Equipment or property damage 	<ul style="list-style-type: none"> Assess risks associated with this task and analyze how to eliminate or reduce the risks Remember to utilize your SWA at any time 	All site personnel
2	Site excavation- See Saw cutting and Jack hammering JSA's if removing concrete or asphalt	<ul style="list-style-type: none"> Property damage Explosion Electrocution Back strain Flying debris 	<ul style="list-style-type: none"> Confirm utility clearance both above and below ground-hand clear soils/ gravel to required depth Utilize good posture and keep lower back in a neutral position while digging Wear Kevlar, or leather gloves Use of appropriate eye/face protection 	Driller, helper
3	Removing soils , concrete, asphalt to place 2' x 2' form for concrete pad Drum up debris	<ul style="list-style-type: none"> Back strain Pinch points Traffic 	<ul style="list-style-type: none"> Use proper lifting techniques when shoveling or lifting debris Keep hands and body clear when transporting drums with dolly or other mechanical means and make sure path is clear prior to moving 	Driller , helper
4	Mixing concrete in a wheel borrow, with a shovel	<ul style="list-style-type: none"> Back strain Inhalation Pinch points Skin irritation 	<ul style="list-style-type: none"> Proper lifting or get help when needed Stand upwind or wear a dusk mask Avoid contact to bare skin with cement products 	Driller, helper
5	Pouring concrete placing flush mount or procap, and finishing surface	<ul style="list-style-type: none"> Back and knee strain Dermal irritants 	<ul style="list-style-type: none"> Maintain good posture when finishing and use knee pads or a mat to protect knees while finishing pad keep cement products from contacting bare skin 	Driller, helper

1. Each Job or Task consists of a set of steps. Be sure to list all the steps in the sequence that they are performed. Specify the equipment or other details to set the basis for the potential (associated) hazards.
2. A hazard is a potential danger. What can go wrong? How can someone get hurt? Consider, but do not limit, the analysis to: **Contact** - victim is struck by or strikes an object; **Caught** - victim is caught on, caught in or caught between objects; **Fall** - victim falls to ground or lower level (includes slips and trips); **Exertion** - excessive strain or stress/ergonomics/lifting techniques; **Exposure** - inhalation/skin hazards. Specify the hazards and do not limit the description to a single word such as "Caught".
3. Aligning with the Job Steps, Task Activity Description, and Potential Hazard columns, describe what actions or procedures are necessary to eliminate or minimize the hazards. Be clear, concise and specific. Use objective, observable, and quantified terms. Avoid subjective general statements such as "be careful" or "use as appropriate".

Site Personnel Participating in JSA Review:

I have participated in the review and discussion of the Job Safety Analysis (JSA) listed on this document and understand the duties I am responsible to fulfill. As part of my work, I know I have the responsibility and obligation to STOP work with a Stop Work Authority (SWA) if conditions change and/or potential hazards have been identified.

Name/Company	Sign	Date



SSE(s) on job: _____

Assigned mentor: _____

Presenter Signature: _____

Date/Time: _____

My signature below indicates that all conditions and requirements listed above have been verified, met, and reviewed with all affected personnel prior to start of work.

Supervisor Signature: _____

Date/Time: _____

Location of Mustering Point: _____

Wind direction (current): _____

GHD Emergency contact (Name and verified phone number): _____

Supervisor Signature documenting Daily Debrief has been completed: _____



Job Safety Analysis (JSA)

Insert Name: Chevron-Well Development

Field staff must review job specific work plan and coordinate with project manager to verify that all up front logistics are completed prior to starting work including, but not limited to, permitting, access agreements, and notification to required contacts (e.g., site managers, inspectors, clients, subcontractors, etc.). Additionally, a tailgate safety meeting must be performed and documented at the beginning of each workday. **Stop, Think, Act, Review (STAR)** must be used prior to any activity. All personnel must possess the appropriate training prior to initiating scheduled tasks. Also consider weather conditions. GHD personnel have the authority and responsibility to use **Stop Work Authority (SWA)**.

Date Issued/Revised:	3/21/2016 1:41:44 PM	Client:	Evergreen Resources Management		
Project Number:	11109626	Created By:	cra\dpsteele	SIM OPS? YES/NO	SSE on site? YES/NO
Project Address:	3144 West Passyunk Avenue Philadelphia				
Key Equipment:					
Task-specific Training:	GHD SMART (BBS) Training, 40-Hour HAZWOPER, 8-Hour Refresher, Hazard Communication, Supervisor shall be training in CPR, First Aid, and have Supervisor Training				

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Type I (Top Impact)	<input checked="" type="checkbox"/> Chemical Protective (ie. Nitrile)	<input checked="" type="checkbox"/> ANSI/CSA Safety Glasses	<input type="checkbox"/> Harness	<input type="checkbox"/> Full Face Mask	<input checked="" type="checkbox"/> Class II	<input type="checkbox"/> Coveralls
<input type="checkbox"/> Type II (Side Impact)	<input type="checkbox"/> Level 1 Light Duty	<input checked="" type="checkbox"/> Goggles/Spoggles	<input type="checkbox"/> Shock Absorb Lanyard	<input type="checkbox"/> Half Face Mask	<input type="checkbox"/> Class III	<input type="checkbox"/> Fire Retardant Clothing (FRC)
<input checked="" type="checkbox"/> Class E (standard)	<input checked="" type="checkbox"/> Level 2 Light Duty with Protection	<input type="checkbox"/> Face Shield	<input type="checkbox"/> Lifeline		<input type="checkbox"/> Anti-Static	<input type="checkbox"/> High Viz Clothing
<input type="checkbox"/> Class G	<input type="checkbox"/> Level 3 Medium Duty	<input type="checkbox"/> Other*		Cartridges	<input type="checkbox"/> FRC	<input checked="" type="checkbox"/> Long Pants
	<input type="checkbox"/> Level 4 Heavy Duty			<input type="checkbox"/> N95	<input type="checkbox"/> PFD	<input checked="" type="checkbox"/> Long Sleeve Shirts
Foot Protection	<input type="checkbox"/> High Viz	Hearing Protection	Arc Flash/Shock Protection	<input type="checkbox"/> P100		<input type="checkbox"/> Paper Tyvek
<input checked="" type="checkbox"/> Industrial Grade Safety Boots	<input checked="" type="checkbox"/> Other*	<input type="checkbox"/> NOT Required	<input type="checkbox"/> Hazard Category 2	<input type="checkbox"/> P95		<input checked="" type="checkbox"/> Polyethylene Tyvek
<input type="checkbox"/> Rubber Boots (industrial grade)		<input type="checkbox"/> Required	<input type="checkbox"/> Hazard Category 4	<input type="checkbox"/> R95		<input type="checkbox"/> Other*
<input type="checkbox"/> Hip Waders				<input type="checkbox"/> Organic Vapour		
	* see key equipment			<input type="checkbox"/> Speciality/Other*		

Project Development Team		Modified by	Reviewed by	Date
Name	Signature			
David Steele				

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
1	Discuss STAR, Stop Work Authority (SWA), Permit to Work process and documents, and Hazard Recognition	<p>1.A – Site personnel not aware of STAR and SWA</p> <p>1.B – Personnel unclear on role assignments regarding implementation of corrective measures</p> <p>1.C – Corrective measures incomplete or incorrectly performed</p>	<p>1.A.1 - Project team to discuss importance of documentation procedures for SWA</p> <p>1.A.2 - Use SWA to stop any unsafe work</p> <p>1.B.1 - Prior to start of work, the person responsible for each corrective measure is assigned and listed on the JSA</p> <p>1.B.2 - All personnel sign JSA and list their names in related Person Responsible column</p> <p>1.C.1 - Prior to start of work the responsible person (as assigned) verifies each corrective measure has been completed by listing their name in the appropriate box on the JSA</p> <p>1.C.2 - Supervisor verifies and signs that each control has been implemented by responsible person</p> <p>1.C.3 - Confirm that all applicable permits have been properly completed and signed by appropriate parties</p>	
2	Coordinate site access	2.A – Work delays	<p>2.A.1 - Notify client PM and respective property owners</p> <p>2.A.2 - Notify other required personnel if applicable (i.e. regulators)</p>	
3	Mobilize with proper equipment/supplies	<p>3.A – Work delay</p> <p>3.B – Improper work performance</p> <p>3.C – Motion- Lifting hazards</p>	<p>3.A.1 - Contact subcontractors to make sure they are aware of their responsibilities to include safety, labor, equipment, supplies, and PPE; select well development technique</p> <p>3.B.1 - Review Site Safety Plan and permit conditions (if applicable)</p> <p>3.B.2 - Review well Construction details</p> <p>3.C.1 - Use proper lifting techniques as discussed or, where applicable, proper moving equipment</p>	

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
4	Perform STAR and safety meeting upon arrival at site	4.A – Insufficient information for all personnel to work safely	4.A.1 - Discuss work steps, OE tenets, and SWA 4.A.2 - Identify SSE employees and the proper course of action along with evacuation routes	
5	Set up any necessary traffic control	5.A – Motion- Struck by a vehicle 5.B – Motion- Vehicle accident as a result of improper traffic control placement	5.A.1 - Use buddy system for placing traffic control 5.A.2 - Never work with your back to traffic 5.A.3 - Wear brightly colored Class 2 traffic vest at all times 5.B.1 - Follow traffic control plan 5.B.2 - Check the effectiveness of the placement after setup	
6	Set up exclusion zone(s)	6.A – Motion- Injury or exposure to public or other onsite personnel 6.B – Motion- Slip hazards 6.C – Motion- Trip Hazards	6.A.1 - Implement exclusion zone setup instructions of HASP 6.A.2 - Use orange traffic cones fence to secure the work area unless working in a high foot traffic area 6.B.1 - Set up clear walking paths between workstations 6.B.2 - Wear boots with adequate tread 6.C.1 - Watch where you step, look for debris which may be covered by brush or rubble	
7	Gauge water levels in wells	7.A – Chemical- Chemical exposure 7.B – Motion- Back strain 7.C – Motion- Traffic hazard	7.A.1 - Don proper PPE in accordance with the HASP 7.A.2 - Monitor air quality in accordance with the HASP 7.B.1 - Bend at the knees and not at the waist 7.C.1 - Keep traffic hazards in view as often as possible and position body facing entrance and exit points 7.C.2 - Pinches from well cover (subgrade wells), stick-up well covers, hand or knee injury	

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
8	Well development set-up	<p>8.A – Mechanical- Personal injury from mechanical failure</p> <p>8.B – Chemical- Exposure to contaminants</p> <p>8.C – Chemical- Cross-contamination</p> <p>8.D – Motion- Back injury if using hand development approach or during pump placement</p> <p>8.E – Gravity- Falling tools if using development rig or drilling rig mast</p>	<p>8.A.1 - Ensure equipment is in proper working order</p> <p>8.B.1 - Don proper PPE in accordance with site-specific plan</p> <p>8.B.2 - Minimize potential for splashing inadvertent discharge of well casing water when lowering downhole pump and tubing</p> <p>8.C.1 - Decontaminate all equipment before and after entering the well</p> <p>8.D.1 - Use proper lifting technique, do not lift over 50 lbs., take breaks and use buddy system</p> <p>8.E.1 - If using cabling on development rig/drill rig, ensure lifting hook safety latches are in-place and functioning correctly.</p> <p>8.E.2 - Check and ensure that rig lifting line cables are operable and that cables are not kinked or otherwise damaged</p>	

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
9	Well development by pumping	<p>9.A – Mechanical- Personal injury from mechanical failure</p> <p>9.B – Chemical- Exposure to contaminants</p> <p>9.C – Chemical- Cross-contamination</p> <p>9.D – Pressure- Pump water discharge line</p>	<p>9.A.1 - Ensure equipment is in proper working order</p> <p>9.B.1 - Don proper PPE in accordance with site-specific plan. Contain water and sludge as required in Scope Of Work.</p> <p>9.B.2 - Ensure that all well development water from hoses and pumps is collected for disposal</p> <p>9.C.1 - Decontaminate all equipment between well development locations; collect all well decon water throughout the project duration</p> <p>9.D.1 - Ensure well development pumping hoses/lines are secured to discharge tanks/drums throughout the well development period</p>	
10	Collect and dispose of collected well development/purge water	<p>10.A – Motion- Lifting hazard</p> <p>10.B – Chemical- Exposure to contaminants</p> <p>10.C – Chemical- Improper storage or disposal</p>	<p>10.A.1 - Use proper lifting techniques as discussed above or where applicable, proper moving equipment</p> <p>10.B.1 - Use PPE and monitoring in accordance with the HASP</p> <p>10.B.2 - Review any necessary instruction for use of on-site treatment systems</p> <p>10.C.1 - Label storage containers properly and locate in isolated area away from traffic and other site functions; communicate location of these drums to project manager</p> <p>10.C.2 - Coordinate for drum pick-up and off-site disposal</p>	

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
11	Clean site/demobilize	11.A – Motion- Traffic hazards 11.B – Motion- Lifting hazard	11.A.1 - Use buddy system as necessary to remove traffic control 11.A.2 - Do not work with your back to traffic 11.A.3 - Wear traffic vest 11.A.4 - Leave site clean of refuse and debris 11.A.5 - Clearly mark/barricade any borings well pads that require curing 11.B.1 - Use proper lifting techniques as discussed above	

- Each Job or Task consists of a set of steps. Be sure to list all the steps in the sequence that they are performed. Specify the equipment or other details to set the basis for the potential (associated) hazards.
- A hazard is a potential danger. What can go wrong? How can someone get hurt? Consider, but do not limit, the analysis to: **Contact** - victim is struck by or strikes an object; **Caught** - victim is caught on, caught in or caught between objects; **Fall** - victim falls to ground or lower level (includes slips and trips); **Exertion** - excessive strain or stress/ergonomics/lifting techniques; **Exposure** - inhalation/skin hazards. Specify the hazards and do not limit the description to a single word such as "Caught".
- Aligning with the Job Steps, Task Activity Description, and Potential Hazard columns, describe what actions or procedures are necessary to eliminate or minimize the hazards. Be clear, concise and specific. Use objective, observable, and quantified terms. Avoid subjective general statements such as "be careful" or "use as appropriate".

Site Personnel Participating in JSA Review:

I have participated in the review and discussion of the Job Safety Analysis (JSA) listed on this document and understand the duties I am responsible to fulfill. As part of my work, I know I have the responsibility and obligation to STOP work with a Stop Work Authority (SWA) if conditions change and/or potential hazards have been identified.

Name/Company	Sign	Date



SSE(s) on job: _____

Assigned mentor: _____

Presenter Signature: _____

Date/Time: _____

My signature below indicates that all conditions and requirements listed above have been verified, met, and reviewed with all affected personnel prior to start of work.

Supervisor Signature: _____

Date/Time: _____

Location of Mustering Point: _____

Wind direction (current): _____

GHD Emergency contact (Name and verified phone number): _____

Supervisor Signature documenting Daily Debrief has been completed: _____



Job Safety Analysis (JSA)

Insert Name: Environmental-
Decontamination of Sampling
Equipment and Personnel
(PPE Level D)

Field staff must review job specific work plan and coordinate with project manager to verify that all up front logistics are completed prior to starting work including, but not limited to, permitting, access agreements, and notification to required contacts (e.g., site managers, inspectors, clients, subcontractors, etc.). Additionally, a tailgate safety meeting must be performed and documented at the beginning of each workday. **Stop, Think, Act, Review (STAR)** must be used prior to any activity. All personnel must possess the appropriate training prior to initiating scheduled tasks. Also consider weather conditions. GHD personnel have the authority and responsibility to use **Stop Work Authority (SWA)**.

Date Issued/Revised:	3/21/2016 1:43:50 PM	Client:	Evergreen Resources Management		
Project Number:	11109626	Created By:	cra\dpsteele	SIM OPS? YES/NO	SSE on site? YES/NO
Project Address:	3144 West Passyunk Avenue Philadelphia				
Key Equipment:	Alconox/Liquinox, brushes				
Task-specific Training:	Decontamination/Site Control; Quality Control/Sampling Plan				

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Type I (Top Impact)	<input checked="" type="checkbox"/> Chemical Protective (ie. Nitrile)	<input checked="" type="checkbox"/> ANSI/CSA Safety Glasses	<input type="checkbox"/> Harness	<input type="checkbox"/> Full Face Mask	<input checked="" type="checkbox"/> Class II	<input type="checkbox"/> Coveralls
<input type="checkbox"/> Type II (Side Impact)	<input type="checkbox"/> Level 1 Light Duty	<input type="checkbox"/> Goggles/Spoggles	<input type="checkbox"/> Shock Absorb Lanyard	<input type="checkbox"/> Half Face Mask	<input type="checkbox"/> Class III	<input type="checkbox"/> Fire Retardant Clothing (FRC)
<input checked="" type="checkbox"/> Class E (standard)	<input type="checkbox"/> Level 2 Light Duty with Protection	<input type="checkbox"/> Face Shield	<input type="checkbox"/> Lifeline		<input type="checkbox"/> Anti- Static	<input type="checkbox"/> High Viz Clothing
<input type="checkbox"/> Class G	<input type="checkbox"/> Level 3 Medium Duty	<input type="checkbox"/> Other*		Cartridges	<input type="checkbox"/> FRC	<input checked="" type="checkbox"/> Long Pants
	<input type="checkbox"/> Level 4 Heavy Duty			<input type="checkbox"/> N95	<input type="checkbox"/> PFD	<input checked="" type="checkbox"/> Long Sleeve Shirts
Foot Protection	<input type="checkbox"/> High Viz	Hearing Protection	Arc Flash/Shock Protection	<input type="checkbox"/> P100		<input type="checkbox"/> Paper Tyvek
<input checked="" type="checkbox"/> Industrial Grade Safety Boots	<input type="checkbox"/> Other*	<input checked="" type="checkbox"/> NOT Required	<input type="checkbox"/> Hazard Category 2	<input type="checkbox"/> P95		<input type="checkbox"/> Polyethylene Tyvek

Hard Hat	Gloves (ANSI/EN 388)	Eye Protections	Fall Protection	APR	Vest	PPE Clothing
<input type="checkbox"/> Rubber Boots (industrial grade)		<input type="checkbox"/> Required	<input type="checkbox"/> Hazard Category 4	<input type="checkbox"/> R95		<input type="checkbox"/> Other*
<input type="checkbox"/> Hip Waders				<input type="checkbox"/> Organic Vapour		
	* see key equipment			<input type="checkbox"/> Speciality/Other*		

Project Development Team		Modified by	Reviewed by	Date
Name	Signature			
David Steele				

Job steps ⁽¹⁾	Task activity	Potential hazard(s) ⁽²⁾	Corrective measure(s) ⁽³⁾	Person responsible (Print first and last names)
1	Decontamination of sampling equipment (including pumps, bailers, tubing, etc.)	<ul style="list-style-type: none"> Contaminant exposure Pinch points Slip/trip/hit/fall hazards Lifting hazards Back injury Manual material handling 	<ul style="list-style-type: none"> Set up decon station to capture any spills to avoid cross contamination and manage wastes Wear appropriate PPE Scrub equipment clean then rinse and verify it is clean and free of contamination Avoid putting hands in or near pinch points Maintain good housekeeping and be aware of surroundings Size up the load; if the object is too large or odd shaped OR is in excess of 50 pounds (23 kg) then assistance (mechanical means, such as a dolly, cart, or a buddy lift) will be required Lift with the legs (bend at the knees and use the leg muscles) to protect the lower back and keep lower back in a neutral position Refer to the HASP for additional lifting techniques 	Sampling Personnel
2	Decontamination of personnel	<ul style="list-style-type: none"> Contaminant exposure Slip/trip/hit/fall hazards 	<ul style="list-style-type: none"> Refer to the HASP for specific procedures but in general start with most contaminated article and remove until inner gloves are the last item left Dispose of used PPE in accordance with site requirements Wash hands and face before eating, drinking, or using tobacco products Take care when removing PPE (boots, gloves, etc.); sit down to remove/change boots as necessary 	Sampling personnel
3	Management of waste derived from decontamination activities	<ul style="list-style-type: none"> Contaminant exposure Lifting hazards Back injury Manual material handling 	<ul style="list-style-type: none"> Containerize decon waste (e.g., water, used PPE) as required Properly dispose of decon fluids (e.g., sediments) Refer to step 1 and the HASP for additional lifting information 	Sampling personnel

- Each Job or Task consists of a set of steps. Be sure to list all the steps in the sequence that they are performed. Specify the equipment or other details to set the basis for the potential (associated) hazards.
- A hazard is a potential danger. What can go wrong? How can someone get hurt? Consider, but do not limit, the analysis to: **Contact** - victim is struck by or strikes an object; **Caught** - victim is caught on, caught in or caught between objects; **Fall** - victim falls to ground or lower level (includes slips and trips); **Exertion** - excessive strain or stress/ergonomics/lifting techniques; **Exposure** - inhalation/skin hazards. Specify the hazards and do not limit the description to a single word such as "Caught".
- Aligning with the Job Steps, Task Activity Description, and Potential Hazard columns, describe what actions or procedures are necessary to eliminate or minimize the hazards. Be clear, concise and specific. Use objective, observable, and quantified terms. Avoid subjective general statements such as "be careful" or "use as appropriate".

Site Personnel Participating in JSA Review:

I have participated in the review and discussion of the Job Safety Analysis (JSA) listed on this document and understand the duties I am responsible to fulfill. As part of my work, I know I have the responsibility and obligation to STOP work with a Stop Work Authority (SWA) if conditions change and/or potential hazards have been identified.

Name/Company	Sign	Date



SSE(s) on job: _____

Assigned mentor: _____

Presenter Signature: _____

Date/Time: _____

My signature below indicates that all conditions and requirements listed above have been verified, met, and reviewed with all affected personnel prior to start of work.

Supervisor Signature: _____

Date/Time: _____

Location of Mustering Point: _____

Wind direction (current): _____

GHD Emergency contact (Name and verified phone number): _____

Supervisor Signature documenting Daily Debrief has been completed: _____

Appendix B

Soil Boring Logs and Well Construction Diagrams

WELL CONSTRUCTION LOG

Project Name: Evergreen Marcus Hook
Project No.: 11110315
Client: Evergreen Marcus Hook
Location: AOI 8


Hole Designation: MW-567
Date Completed: 4/27/2016
Drilling Method: Hollow stem auger
GHD Supervisor: Matthew Marcus

Survey Information:

top of inner casing: _____
ground: _____

longitude: _____
latitude: _____

NOT TO SCALE



STRATIGRAPHY LOG (OVERBURDEN)

Page 1 of 1

Project Name: AOI 8 Marcus Hook
 Project Number: 11110315
 Client: Evergreen
 Location: AOI 8

Drilling Contractor:
 Driller:
 Drilling Method: Backhoe/Hollow Stem Auger
 Surface Elevation:

Hole Designation: MW-567
 Date/Time Started: 4/21/2016 07:56
 Date Completed: 4/27/2016
 CRA Supervisor: Matthew Marcus

L I T H O L O G Y	Stratigraphic Intervals (depths in ft bgs)			SAMPLE DESCRIPTION	SAMPLE DETAILS								S I L T C O N T E N T L (ppm)	P I D	N - V A L U E
	F R O M	A T	O		S M P L E #	S A M P L E G	Penetration Record Split Spoon Blows				R E C O V E R Y	S I L T C O N T E N T L			
	0		2	Sandy silt with pebbles and cobbles, dry, fill material. Dark brown. Light odor, no staining			6"	6"	6"	6"		3.3			
	2		3	Sandy silt with pebbles, chunks of gray clay. Mostly light brown. Light odor, no staining								5.3			
	3		4.5	Clayey silt with sands and pebbles. Gray to light brown, moist, light odor, no staining.								16.1			
	4.5		6	Clayey silt with sands/gravels/pebbles. Light brown/gray. Heavy staining, strong odor.								138			
	6		7	Clayey silts, with sands/gravels. Light brown to gray, strong odor and staining. Moist								153			
	7		8	Gray clay with brown with brown silts and sands. Moist. Strong odor and staining.								314			
	8		12	8-8.5': Sandy silty clay, moist, strong odor, 205 ppm. 8.5-10' Gray clay, with trace silts and sands. Odor, moist. 485 ppm. 10-12': Same								205, 485, 242, 124, 220, 268			
	12		16	12-13.5' gray sandy clay, pockets of coarse gray sand, sheen, odor. 13.5-16' Light brown sand, no odor or sheen, wet							56.7, 63, 23.9, 4.5 3				
	16		20	Light brown sand, with silts, wet. 16-18.5': Light brown sand, trace gravels. 18.5-19': Find sand, tannish/light brown, light odor, no staining.								11.9, 11.7, 11.9, 8.5, 5.8			

Notes and Comments

HA - Hand Auger

SS - Split-Spoon

NA - Not Available

NIR: No Instrument Response.

WH - Weight of Hammer



WELL CONSTRUCTION LOG


Project Name: Evergreen Marcus Hook
 Project No.: 11110315
 Client: Evergreen Marcus Hook
 Location: AOI 8
 Survey Information:

Hole Designation: MW-568
 Date Completed: 4/27/2016
 Drilling Method: Hollow stem auger
 GHD Supervisor: Matthew Marcus

top of inner casing: _____
 ground: _____

longitude: _____
 latitude: _____

NOT TO SCALE



STRATIGRAPHY LOG (OVERBURDEN)

Page 1 of 1

Project Name: AOI 8 Marcus Hook

Project Number: 11110315

Client: Evergreen

Location: AOI 8

Drilling Contractor:

Driller:

Drilling Method: Backhoe/Hollow Stem Auger

Surface Elevation:

Hole Designation: MW-568

Date/Time Started: 4/20/2016 13:20

Date Completed: 4/27/2016

CRA Supervisor: Matthew Marcus

L I T H O L O G Y	Stratigraphic Intervals (depths in ft bgs)			SAMPLE DESCRIPTION	SAMPLE DETAILS								S I A N T P E L R E V A L	P I D (ppm)	N - V A L U E
					O r d e r o f D e s c r i p t o r s : P r i m a r y C o m p o n e n t /S e c o n d a r y C o m p o n e n t s R e l a t i v e D e n s i t y /C o n s i s t e n c y , G r a i n S i z e /P l a s t i c i t y , G r a d a t i o n /S t r u c t u r e , C o l o r , M o i s t u r e C o n t e n t , S u p p l e m e n t a r y D e s c r i p t o r s	S M A E M P H L O I D N G #	Penetration Record Split Spoon Blows				R E C O V E R Y				
								6"	6"	6"		6"			
	0		2	Sandy silt with some pebbles, some staining light odor, dry									0.1		
	2		3	Clayey silt, dark brown, moist, no staining or odor									0		
	3		4	Clayey silt, light brown with trace sands and pebbles, some chunks of clay. No staining or odor									0		
	4		5	Same, with more clay content, dry.									0		
	5		6	Silts with clay, trace sands. Light brown grading to orange.									0		
	6		7	Same, clayey silt, orange, dry.									0		
	7		8	Silty clay, clay is grayish, silt, orangish, moist.									0		
	8		12	8-8.66': Clayey silt, orange, wet, no odor or staining. 8.66-9.75': Gravels to light brown fine sands, silt, wet. 9.75-12': Grades from light brown to gray silts to sand. Petro odor at ~11'. Wet.							48"		0, 0, 0, 4.6		
	12		16	12-13.3': Fine sand, brown/gray, light petro odor, wet. No stain. 13.3-14.25': Coarser sand with gravel, light odor, wet. 14.25-16': Sands grade to gravelly/silty, gray/black, dense soil: weathered mica? Wet, no odor.							48"		0, 0, 0.5, 0.1, 0		

Notes and Comments

HA - Hand Auger

SS - Split-Spoon

NA - Not Available

NIR: No Instrument Response.

WH - Weight of Hammer



WELL CONSTRUCTION LOG

Project Name: Evergreen Marcus Hook
Project No.: 11110315
Client: Evergreen Marcus Hook
Location: AOI 8


Hole Designation: MW-569
Date Completed: 4/26/2016
Drilling Method: Hollow stem auger
GHD Supervisor: Matthew Marcus

Survey Information:

top of inner casing: _____
ground: _____

longitude: _____
latitude: _____

NOT TO SCALE



STRATIGRAPHY LOG (OVERBURDEN)

Page 1 of 1

Project Name: AOI 8 Marcus Hook
 Project Number: 11110315
 Client: Evergreen
 Location: AOI 8

Drilling Contractor:
 Driller:
 Drilling Method: Backhoe/Hollow Stem Auger
 Surface Elevation:

Hole Designation: MW-569
 Date/Time Started: 4/20/2016 12:00
 Date Completed: 4/26/2016
 CRA Supervisor: Matthew Marcus

L I T H O L O G Y	Stratigraphic Intervals (depths in ft bgs)			SAMPLE DESCRIPTION	SAMPLE DETAILS								S I A N M T P E L R E V A L	P I D (ppm)	N - V A L U E
					S A M P L E #	S M A T P H O L I D G	Penetration Record Split Spoon Blows				R E C O V E R Y				
	F R O M	A T	O	Order of Descriptors: Primary Component/Secondary Components Relative Density/Consistency, Grain Size/Plasticity, Gradation/Structure, Color, Moisture Content, Supplementary Descriptors			6"	6"	6"	6"					
	0		2	Sandy silt loam with pebbles and cobbles, dark brown, moist. No odor or staining									0		
	2		3	Same									0		
	3		4	Same, moist, dark brown silt with sands, trace clay and pebbles									0		
	4		5	Same. Mesh netting in this interval. Chunks of gray clay									0		
	5		6	Same, with more gray clay chunks									0		
	6		7	Same, with chunks of black stained clayey silts with odor									0		
	7		8	same as above, with occasional large rocks. Moist, no odor or staining.									0		
	8		12	0"-8": Silty sand, light brown. Moist to wet. 8"-16": clayey sand, light brown. 16"-31": Mottled clay with silts and sands, reddish with gray and orange streaks. 31"-38": Greenish gray clay, with trace silts and sands									0		
	12		13	Weathered rock, likely mica schist. Gravelly/sandy, black and white with shiny flecks, trace brown silts. Refusal at 13'											

Notes and Comments

HA - Hand Auger

SS - Split-Spoon

NA - Not Available

NIR: No Instrument Response.

WH - Weight of Hammer



WELL CONSTRUCTION LOG


Project Name: Evergreen Marcus Hook
Project No.: 11110315
Client: Evergreen Marcus Hook
Location: AOI 8
Survey Information:

Hole Designation: MW-570
Date Completed: 4/26/2016
Drilling Method: Hollow stem auger
GHD Supervisor: Matthew Marcus

top of inner casing: _____
ground: _____

longitude: _____
latitude: _____

NOT TO SCALE



STRATIGRAPHY LOG (OVERBURDEN)

Page 1 of 1

Project Name: AOI 8 Marcus Hook
 Project Number: 11110315
 Client: Evergreen
 Location: AOI 8

Drilling Contractor: _____
 Driller: _____
 Drilling Method: Backhoe/Hollow Stem Auger
 Surface Elevation: _____

Hole Designation: MW-570
 Date/Time Started: 4/20/2016 11:00
 Date Completed: 4/26/2016
 CRA Supervisor: Matthew Marcus

L I T H O L O G Y	Stratigraphic Intervals (depths in ft bgs)			SAMPLE DESCRIPTION Order of Descriptors: Primary Component/Secondary Components Relative Density/Consistency, Grain Size/Plasticity, Gradation/Structure, Color, Moisture Content, Supplementary Descriptors	SAMPLE DETAILS								S I A N M T P E L R E V A L	P I D (ppm)	N - V A L U E
					S A M P L E #	S M A E M P H O L O I D N G	Penetration Record Split Spoon Blows				R E C O V E R Y				
	6"	6"	6"				6"								
0		2	Silt loam, sandy with pebble fill. Light brown. Dry with trace organics			6"	6"	6"	6"			0			
2		3	Same as above, with some staining, light petro odor.									0.3			
3		4	Sandy silt, mostly stained, light odor. Ground water enters hole									3.6			
4		5	Clayey silt, dark gray to brown, wet with trace organics. Light odor, with some staining									0			
5		6	Clayey silt, chunks of pure gray clay, patches of dark brown silts, wet. Occasional cobbles									0			
6		7	Same as 6-7									0			
7		8	Clays and silts with trace sands. Light brown. No odor or staining									0			
8		12	0-19": Gray, coarse sand, wet. 19"-30": Gray grades to light tan, finer sand, wet. 30"-40": Grades to light brown, finer sand, some light brown silt, wet, no odor or staining.							40"		0.2, 0.1, 0.0, 0.0, 0.2			
12		16	No recovery. Residue is light brown wet sand.							0					

Notes and Comments

HA - Hand Auger

SS - Split-Spoon

NA - Not Available

NIR: No Instrument Response.

WH - Weight of Hammer



WELL CONSTRUCTION LOG

Project Name: Evergreen Marcus Hook
Project No.: 11110315
Client: Evergreen Marcus Hook
Location: AOI 8


Hole Designation: MW-571
Date Completed: 4/25/2016
Drilling Method: Hollow stem auger
GHD Supervisor: Matthew Marcus

Survey Information:

top of inner casing: _____
ground: _____

longitude: _____
latitude: _____

NOT TO SCALE



STRATIGRAPHY LOG (OVERBURDEN)

Page 1 of 1

Project Name: AOI 8 Marcus Hook
 Project Number: 11110315
 Client: Evergreen
 Location: AOI 8

Drilling Contractor:
 Driller:
 Drilling Method: Backhoe/Hollow Stem Auger
 Surface Elevation:

Hole Designation: MW-571
 Date/Time Started: 4/20/2016 09:00
 Date Completed: 4/25/2016
 CRA Supervisor: Matthew Marcus

L I T H O L O G Y	Stratigraphic Intervals (depths in ft bgs)			SAMPLE DESCRIPTION	SAMPLE DETAILS								S I A N M T P E L R E V A L	P I D (ppm)	N - V A L U E
	F R O M	A T	O	Order of Descriptors: Primary Component/Secondary Components Relative Density/Consistency, Grain Size/Plasticity, Gradation/Structure, Color, Moisture Content, Supplementary Descriptors	S A M P L E #	S M A T P H O L I D G	Penetration Record Split Spoon Blows				R E C O V E R Y				
							6"	6"	6"	6"					
	0		1	Sandy silt with gravel, light brown, dry. Pebble fill and fabric cloth at 1' bgs.									0		
	1		2	Sandy silt, dark brown. Clumps of grey, crumbly silty clay fill material. Moist. Pebble/rock fill										0	
	2		3	Sandy silt, some clay in dark gray clumps, moist										0	
	3		5	Sandy silt, some clay, pebbles, dark brown. Moist, no odor or staining										2.7	
	5		6	Dark brown sandy silt with clumps of gray clay, some pebbles throughout										3.1	
	6		7	Mostly gray clay, with some sands and silt										2.1	
	7		8	Mostly gray clay, some dark brown silts, with trace sand and pebbles. No odor or staining. Moist										0	
	8		9.3	Silty clay, gray with brown streaks. No odor or staining. Moist										0.2, 0.5	
	9.3		12	Tan sand, wet. Water table at roughly 9.3'										1.0, 0.2, 0.2, 5.5	
	12		16	Fine gray sand, with a light non-petro odor. Wet.										5.7, 3.3, 3.0, 8.9, 2.3, 4.5	

Notes and Comments

HA - Hand Auger

SS - Split-Spoon

NA - Not Available

NIR: No Instrument Response.

WH - Weight of Hammer



Appendix C

Pennsylvania Natural Diversity Inventory (PNDI)

Environmental Review

1. PROJECT INFORMATION

Project Name: **Marcus Hook AOI 8**

Date of Review: **9/23/2016 12:10:37 PM**

Project Category: **Hazardous Waste Clean-up, Site Remediation, and Reclamation, Other**

Project Area: **22.97 acres**

County(s): **Delaware**

Township/Municipality(s): **MARCUS HOOK**

ZIP Code: **19061**

Quadrangle Name(s): **MARCUS HOOK**

Watersheds HUC 8: **Lower Delaware**

Watersheds HUC 12: **Oldmans Creek-Delaware River**

Decimal Degrees: **39.815342, -75.429249**

Degrees Minutes Seconds: **39° 48' 55.2297" N, 75° 25' 45.2969" W**

2. SEARCH RESULTS

Agency	Results	Response
PA Game Commission	No Known Impact	No Further Review Required
PA Department of Conservation and Natural Resources	No Known Impact	No Further Review Required
PA Fish and Boat Commission	No Known Impact	No Further Review Required
U.S. Fish and Wildlife Service	No Known Impact	No Further Review Required

As summarized above, Pennsylvania Natural Diversity Inventory (PNDI) records indicate no known impacts to threatened and endangered species and/or special concern species and resources within the project area. Therefore, based on the information you provided, no further coordination is required with the jurisdictional agencies. This response does not reflect potential agency concerns regarding impacts to other ecological resources, such as wetlands.


Note that regardless of PNDI search results, projects requiring a Chapter 105 DEP individual permit or GP 5, 6, 7, 8, 9 or 11 in certain counties (Adams, Berks, Bucks, Carbon, Chester, Cumberland, Delaware, Lancaster, Lebanon, Lehigh, Monroe, Montgomery, Northampton, Schuylkill and York) must comply with the bog turtle habitat screening requirements of the PASPGP.

Marcus Hook AOI 8






- Project Boundary
- Buffered Project Boundary

Service Layer Credits: Sources: Esri, HERE, DeLorme, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, MapmyIndia, © OpenStreetMap contributors, and the GIS User Community
Source: Esri, DigitalGlobe, GeoEye, Earthstar Geographics, CNES/Airbus DS, USDA,




Marcus Hook AOI 8



-  Project Boundary
-  Buffered Project Boundary

Service Layer Credits: Sources: Esri, HERE, DeLorme, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), swisstopo, MapmyIndia, © OpenStreetMap contributors, and the GIS User Community



3. AGENCY COMMENTS

Regardless of whether a DEP permit is necessary for this proposed project, any potential impacts to threatened and endangered species and/or special concern species and resources must be resolved with the appropriate jurisdictional agency. In some cases, a permit or authorization from the jurisdictional agency may be needed if adverse impacts to these species and habitats cannot be avoided.

These agency determinations and responses are **valid for two years** (from the date of the review), and are based on the project information that was provided, including the exact project location; the project type, description, and features; and any responses to questions that were generated during this search. If any of the following change: 1) project location, 2) project size or configuration, 3) project type, or 4) responses to the questions that were asked during the online review, the results of this review are not valid, and the review must be searched again via the PNDI Environmental Review Tool and resubmitted to the jurisdictional agencies. The PNDI tool is a primary screening tool, and a desktop review may reveal more or fewer impacts than what is listed on this PNDI receipt. The jurisdictional agencies **strongly advise against** conducting surveys for the species listed on the receipt prior to consultation with the agencies.

PA Game Commission

RESPONSE:

No Impact is anticipated to threatened and endangered species and/or special concern species and resources.

PA Department of Conservation and Natural Resources

RESPONSE:

No Impact is anticipated to threatened and endangered species and/or special concern species and resources.

PA Fish and Boat Commission

RESPONSE:

No Impact is anticipated to threatened and endangered species and/or special concern species and resources.

U.S. Fish and Wildlife Service

RESPONSE:

No impacts to **federally** listed or proposed species are anticipated. Therefore, no further consultation/coordination under the Endangered Species Act (87 Stat. 884, as amended; 16 U.S.C. 1531 et seq. is required. Because no take of federally listed species is anticipated, none is authorized. This response does not reflect potential Fish and Wildlife Service concerns under the Fish and Wildlife Coordination Act or other authorities.

4. DEP INFORMATION

The Pa Department of Environmental Protection (DEP) requires that a signed copy of this receipt, along with any required documentation from jurisdictional agencies concerning resolution of potential impacts, be submitted with applications for permits requiring PNDI review. Two review options are available to permit applicants for handling PNDI coordination in conjunction with DEP's permit review process involving either T&E Species or species of special concern. Under sequential review, the permit applicant performs a PNDI screening and completes all coordination with the appropriate jurisdictional agencies prior to submitting the permit application. The applicant will include with its application, both a PNDI receipt and/or a clearance letter from the jurisdictional agency if the PNDI Receipt shows a Potential Impact to a species or the applicant chooses to obtain letters directly from the jurisdictional agencies. Under concurrent review, DEP, where feasible, will allow technical review of the permit to occur concurrently with the T&E species consultation with the jurisdictional agency. The applicant must still supply a copy of the PNDI Receipt with its permit application. The PNDI Receipt should also be submitted to the appropriate agency according to directions on the PNDI Receipt. The applicant and the jurisdictional agency will work together to resolve the potential impact(s). See the DEP PNDI policy at <https://conservationexplorer.dcnr.pa.gov/content/resources>.

5. ADDITIONAL INFORMATION

The PNDI environmental review website is a preliminary screening tool. There are often delays in updating species status classifications. Because the proposed status represents the best available information regarding the conservation status of the species, state jurisdictional agency staff give the proposed statuses at least the same consideration as the current legal status. If surveys or further information reveal that a threatened and endangered and/or special concern species and resources exist in your project area, contact the appropriate jurisdictional agency/agencies immediately to identify and resolve any impacts.

For a list of species known to occur in the county where your project is located, please see the species lists by county found on the PA Natural Heritage Program (PNHP) home page (www.naturalheritage.state.pa.us). Also note that the PNDI Environmental Review Tool only contains information about species occurrences that have actually been reported to the PNHP.

6. AGENCY CONTACT INFORMATION

PA Department of Conservation and Natural Resources

Bureau of Forestry, Ecological Services Section
400 Market Street, PO Box 8552
Harrisburg, PA 17105-8552
Email: RA-HeritageReview@pa.gov
Fax: (717) 772-0271

PA Fish and Boat Commission

Division of Environmental Services
450 Robinson Lane, Bellefonte, PA 16823
Email: RA-FBPACENOTIFY@pa.gov

U.S. Fish and Wildlife Service

Pennsylvania Field Office
Endangered Species Section
110 Radnor Rd; Suite 101
State College, PA 16801
NO Faxes Please

PA Game Commission

Bureau of Wildlife Habitat Management
Division of Environmental Planning and Habitat Protection
2001 Elmerton Avenue, Harrisburg, PA 17110-9797
Email: RA-PGC_PNDI@pa.gov
NO Faxes Please

7. PROJECT CONTACT INFORMATION

Name: _____
Company/Business Name: _____
Address: _____
City, State, Zip: _____
Phone: (____) _____ Fax: (____) _____
Email: _____

8. CERTIFICATION

I certify that ALL of the project information contained in this receipt (including project location, project size/configuration, project type, answers to questions) is true, accurate and complete. In addition, if the project type, location, size or configuration changes, or if the answers to any questions that were asked during this online review change, I agree to re-do the online environmental review.

applicant/project proponent signature

date

Appendix D

QA Plan/Field SOPs



Quality Assurance/Quality Control Plan

Marcus Hook Industrial Complex and
Philadelphia Energy Solutions (PES) – Philadelphia
Refinery

Evergreen

GHD

410 Eagleview Boulevard, Suite 110 Exton Pennsylvania 19341 United States
11102641 | Report No 1 | April 4, 2016

Table of Contents

1.	Introduction.....	1
2.	Quality Control Requirements	1
2.1	Field Sampling Quality Control	1
2.2	Analytical Quality Control.....	1
3.	Data Verification/Validation and Usability	2
3.1	Laboratory Data Review, Verification, and Validation Requirements.....	2
3.2	Groundwater Sampling Methods	4
3.3	Data Updates in the Electronic Data Deliverables.....	5
3.4	Validation Qualifiers	5
3.5	Verification and Validation Summary.....	7
3.6	Verification and Validation Summary.....	8

1. Introduction

This Quality Assurance/Quality Control (QA/QC) Plan outlines the procedures developed to ensure the collection and analysis of quality data for the completion of investigations completed under the United States Environmental Protection Agency (USEPA) Resource Conservation and Recovery Act (RCRA) program, Pennsylvania Department of Environmental Protection (PADEP) Act 2 program and Pennsylvania and Delaware's Tank programs at the Marcus Hook Industrial Complex (MHIC) and the Philadelphia Energy Solutions – Philadelphia Refinery (PES Refinery). This document shall be used in conjunction with the Site-Specific Work Plans and Standard Operating Procedures (SOPs) prepared for each site.

The QA/QC Plan is a planning document that provides a "blueprint" for obtaining the type and quality of data needed to support environmental decision making. The QA/QC Plan integrates relevant technical and quality aspects of a project and documents quality assurance and quality control.

2. Quality Control Requirements

The field and laboratory QC requirements for the monitoring activities are discussed in the following subsections. Specific QC checks and acceptance criteria are provided in the referenced analytical methods.

2.1 Field Sampling Quality Control

Field QC requirements include analyzing reference standards for instrument calibration and for routine calibration checks. Field QC samples for this project include, field duplicate samples to assess the overall precision of the sampling and analysis event, equipment rinse blanks to ensure proper cleaning of equipment is conducted between samples to avoid potential cross-contamination, and trip blank samples to monitor cross-contamination of water samples by VOCs. The frequency of collection of these field QC samples is summarized in the Site Specific Field Activities and SOPs, to reflect that a duplicate will be collected 1 in 20 samples and a trip blank will be collected per every sample shipment (cooler).

2.2 Analytical Quality Control

The laboratory QC requirements for the analyses include analyzing method blanks, instrument performance checks, initial calibration standards, calibration verification standards, internal standards, surrogate compound spikes, interference check samples, serial dilution samples, MS/MSD samples, and LCSs. The acceptance criteria for MS/MSD, LCSs, and surrogate compounds will be generated by the laboratory and included in the laboratory reports.

3. Data Verification/Validation and Usability

All field and laboratory data will be reviewed, verified, and/or validated. These terms are defined as follows:

- Data review is the in-house examination to ensure that the data have been recorded, transmitted, and processed correctly.
- Data verification is the process for evaluating the completeness, correctness, and conformance/compliance of a specific data set against the method, procedural, or contractual specifications.
- Data validation is an analyte- and sample-specific process that extends the evaluation of data beyond method, procedure, or contractual compliance (i.e., data verification) to determine the quality of a specific data set relative to the end use.

Field data and logbooks may be reviewed to ensure that the requirements of the sampling program, including the number of samples and locations, sampling, and sample handling procedures, were fulfilled.

Data verification/validation and usability assessments will be performed to ensure that the data are scientifically defensible, properly documented, of known quality, and meet the project objectives are described in the following sections.

3.1 Laboratory Data Review, Verification, and Validation Requirements

Data review, verification and validation of the analytical data will be performed by each Consultant completing the field activities. The evaluation and action criteria specified in this document will be used for validating the data. Qualifiers assigned to the data will be consistent with the data qualifiers specified in the validation guideline.

Stage 1 Verification and Validation Checks

One hundred percent of the sample results will go through a Stage 1 validation (verification). As part of the data management process, each consultant will complete verification based on the Superfund Guidance for Labeling Externally Validated Laboratory Analytical Data (<http://www.epa.gov/superfund/policy/pdfs/EPA-540-R-08-005.pdf>). Data verification will consist of the following items based on the guidance stated.

Stage 1 validation of the laboratory analytical data package consists of verification and validation checks for the compliance of sample receipt conditions, sample characteristics (e.g., percent moisture), and analytical results (with associated information). It is recommended that the following minimum baseline checks (as relevant) be performed on the laboratory analytical data package received for a Stage 1 validation label:

1. Documentation identifies the laboratory receiving and conducting analyses, and includes documentation for all samples submitted by the project or requester for analyses.
2. Requested analytical methods were performed and the analysis dates are present.

3. Requested target analyte results are reported along with the original laboratory data qualifiers and data qualifier definitions for each reported result (and the uncertainty of each result and clear indication of the type of uncertainty reported if required).
4. Requested target analyte result units are reported (along with their associated uncertainty units if required).
5. Requested reporting limits for all samples are present and results at and below the requested (required) reporting limits are clearly identified (including sample detection limits if required).
6. Sampling dates (including times if needed), date and time of laboratory receipt of samples, and sample conditions upon receipt at the laboratory (including preservation, pH and temperature) are documented.
7. Sample results are evaluated by comparing sample conditions upon receipt at the laboratory (e.g., preservation checks) and sample characteristics (e.g., percent moisture) to the requirements and guidelines present in national or regional data validation documents, analytical method(s) or contract.

Stage 2 Verification and Validation Checks

A minimum of 10 percent of the samples will go through a Stage 2 validation. When a laboratory work order is selected, the entire work order will undergo Stage 2 validation. A minimum of 10 percent of the samples will be flagged for VUA. Laboratory work orders or sample delivery groups (SDGs) that are selected for VUA will undergo validation based on the Superfund Program's National Functional Guidelines.

The selection of samples that will undergo VUA process is designed to meet the needs of the site investigation, characterization, remediation, and closure programs, such as tank closures. Sampling that falls outside these programs will not undergo the VUA process. This includes samples that are collected for permit compliance, such as RCRA and effluent wastewater, as well as product samples, onsite soil reuse samples, and waste characterization samples.

Ten percent of samples will be selected based on the following hierarchy:

1. Sample package that will be selected will contain a field duplicate sample.
2. Sample package will be selected at random.

Samples that are collected in the field will provide the best information for completing the VUA reports. The hierarchy is designed to provide the most useful information regarding sample analysis integrity. Therefore, field duplicate samples have been assigned the highest priority. However, field duplicate samples will only be prepared for groundwater samples, not for soil sampling events. If there are insufficient field duplicate samples to meet the 10 percent goal, samples with field blanks will be selected. Sample selection will be a subset of samples collected for a characterization or closure events and will be calculated by taking 10 percent of the number of samples collected. For program efficiency, entire SDGs will be selected for submission in the VUA process. Individual samples should not be selected and processed unless there is an overriding reason to do so. The exception to this scenario will be Aquaterra, where the consultant company working with Aquaterra will validate the samples collected by them.

Stage 2 data validation includes a review of the following QC data deliverables:

1. Technical Holding Times
2. Method Blanks
3. Surrogate Spikes
4. MS/MSD Results
5. LCS Samples
6. Field Duplicates
7. Trip and Equipment Blank Samples

Stage 4 Verification and Validation Checks

Additional data validation may be completed for selected sites and/or sampling events, up to EPA Level 4 data review, which includes all of the elements of a Stage 2 Validation and

1. Evaluation of instrument performance checks (GC/MS)
2. Initial and continuing calibration checks (organic and inorganic analyses)
3. Review of internal standards (GC/MS)
4. Instrument blanks (inorganics)
5. Interference check samples (metals)
6. Recalculations of sample results and reporting limits.

3.2 Groundwater Sampling Methods

Company specific valid codes will be added to the database. This will allow quick identification of the consultant that has performed the verification and/or VUA. Stantec may append additional codes for data management purposes to the codes provided in dt_result table approval_code field. Valid codes are as follows:

Langan:

- LAN1 – Historical data collected by Langan - Level 1 Validation (Verification)
- LAN-VER – Langan performed verification
- LAN-USB – Langan performed usability

GHD:

- GHD-VER – GHD performed verification
- GHD-USB – GHD performed usability

Stantec:

- STN-VER – Stantec performed verification
- STN-USB – Stantec performed usability

This methodology creates a means for consultants to perform verification and usability on data collected by another consultant.

3.3 Data Updates in the Electronic Data Deliverables

All consultants will request EQulS 4 file format Electronic Data Deliverables (EDDs) for data management from the analytical laboratories. In order to facilitate the data updates in the database, the following methodology is proposed.

1. The consultant chemist / chemist team will open the .RES file for the EDD that has been selected to be validated for usability. The file can be opened using Excel, Access, Notepad or similar tool. Although, it is a best practice to open the file in a way to preserve the textual nature of the EDD, it is unnecessary to do it in this case.
2. The chemist will use the result_comment field in the .RES file to enter the qualifiers associated with the record and add a semicolon as a delimiter (;) followed by the reason code for the qualification (e.g., U;SUR).
3. The .RES file is to be saved with a .USB extension at the end of the file. This file is to be separate from the original .RES file provided and should not be used to over-write the original .RES file that was sent with the EDD. This will result in the laboratory work order undergoing VUA having five files instead of four for the EDD. For example:
 - 1234.SMP
 - 1234.TST
 - 1234.BCH
 - 1234.RES
 - 1234.RES.USB
4. Stantec will use the fifth file to update the database with the appropriate qualifiers and codes in validator_qualifiers and approval_a through approval_d fields in dt_result table in the database.
5. Stantec will also change the validated y/n field in dt_result table in the database for the particular EDD.

3.4 Validation Qualifiers

The following qualifiers should be used during the validation/usability process. These are based on the NFGs and commonly used qualifiers.

Data Qualifiers and Definitions

- | | |
|----|---|
| U | The analyte was analyzed for, but was not detected above the level of the reported sample quantitation limit. |
| J | The result is an estimated quantity. The associated numerical value is the approximate concentration of the analyte in the sample. |
| UJ | The analyte was analyzed for, but was not detected. The reported quantitation limit is approximate and may be inaccurate or imprecise. |
| NJ | The analyte has been "tentatively identified" or "presumptively identified" as present and the associated numerical value is the estimated concentration in the sample. |

- R The data are unusable. The sample results are rejected due to serious deficiencies in meeting QC criteria. The analyte may or may not be present in the sample.
- B The analyte was detected in the method, field, and/or trip blank.

If additional qualifiers are required, please forward the suggestions to the Stantec PM (Jennifer Menges) or the Stantec Data Management Lead (Andrew Bradley), and they will be added to the list of approved codes.

Reason codes

A list of reason codes are available for validation. If additional codes are required, please forward the suggestions to the Stantec PM (Jennifer Menges) or the Stantec Data Management Lead (Andrew Bradley) for addition to the list of approved codes.

Submitting data, Validation CODES for inclusion in the database

EDDs will be submitted to the database using the SharePoint portal intake forms. The appropriate qualifiers and codes that have been added to the result_comment field in the .RES.USB file will be included in the submission.

Data Usability Report

Data usability reports will be generated as required for characterization or final reporting to the agencies. Each consultant will be responsible for their own VUA report. A VUA report template will be created for consistency in reporting. The template will be completed using the Data Usability Checklist completed by the chemist.

Revision History

Revision Record			
Revision	Description	Prepared By	
1.0	Initial creation of document	Gus Sukkurwala/Jennifer Menges/ Andrew Bradley	5/31/2015

Reason Codes

Reason Code	Reason Description
General Use	
EC	Result exceeds the calibration range.
HT	Holding time requirement was not met
MB	Method blank or preparation blank contamination
LCS	Laboratory control sample evaluation criteria not met
FB	Field blank contamination
RB	Rinsate blank contamination
SQL	The analysis meets all qualitative identification criteria, but the measured concentration is less than the reporting limit.
FD	Field duplicate evaluation criteria not met
TvP	Total to Partial criteria not met
RL	Reporting limit exceeds decision criteria (for non-detects)

Reason Code	Reason Description
Inorganic Methods	
ICV	Initial calibration verification evaluation criteria not met
CCV	Continuing calibration verification evaluation criteria not met
CCB	Continuing calibration blank contamination
PB	Preparation Blank
ICS	Interference check sample evaluation criteria not met
D	Laboratory duplicate or spike duplicate precision evaluation criteria not met
MS	Matrix spike recovery outside acceptance range
PDS	Post-digestion spike recovery outside acceptance range
MSA	Method of standard additions correction coefficient $\neq 0.995$
DL	Serial dilution results did not meet evaluation criteria
Organic Methods	
TUNE	Instrument performance (tuning) criteria not met
ICAL	Initial calibration evaluation criteria not met
CCAL	Continuing calibration evaluation criteria not met
SUR	Surrogate recovery outside acceptance range
MS/SD	Matrix spike/matrix spike duplicate precision criteria not met
MS	Matrix spike recovery outside acceptance range
IS	Internal standard evaluation criteria not met
LM	The PFK lock mass SICPs indicate that ion suppression evident
ID	Target compound identification criteria not met
Results Reported for Analytes Analyzed Multiple Times	
NSR	Not selected for reporting because the result was qualified as unusable
NSDL	Not selected for reporting because diluted result was selected for reporting
NSQ	Not selected for reporting because result was lesser quality based on data validation
NSO	Not selected for reporting because of other reason
Bias Codes	
H	Bias in sample result likely to be high
L	Bias in sample result likely to be low
I	Bias in sample result is indeterminate

3.5 Verification and Validation Summary

Field data will be verified by reviewing field documentation and chain-of-custody records. Data from direct-reading field instruments will be verified by reviewing calibration and operating records and the QC data specified in this QA/QC Plan.

Verification of sample collection procedures consists of reviewing sample collection documentation for compliance with the requirements of the workplan and QA/QC Plan. If alternate sampling procedures were used, the acceptability of the procedure will be evaluated to determine the affect on the usability of the data. Data usability will not be affected if the procedure used is determined to be an acceptable alternative that fulfills the measurement performance criteria in this QA/QC Plan.

The results of the data verification/ validation procedure will identify data that do not meet the measurement performance criteria of this QA/QC Plan. Data verification/validation will determine whether the data are acceptable, of limited usability (qualified as estimated), or rejected. Data

qualified as estimated will be reviewed and a discussion of the usability of estimated data will be included in the data validation report.

Data determined to be unusable may require corrective action to be taken. Potential types of corrective action may include resampling by the field team or reanalysis of samples by the laboratory. The corrective actions taken are dependent upon the ability to mobilize the field team and whether or not the data are critical for project DQOs to be achieved.

3.6 Verification and Validation Summary

Data use limitations will be identified in data usability write up. Field information will be reviewed to ensure that all sampling procedures and field measurements were conducted in accordance with the requirements of the Site Specific Field Activities and SOPs. Field measurements obtained or data from samples collected using procedures inconsistent with the requirements of the Site Specific Field Activities and SOPs will be evaluated and may require that additional samples are collected or the use of the data be restricted.

**EVERGREEN FIELD PROCEDURES
PHILADELPHIA REFINERY COMPLEX
PHILADELPHIA, PENNSYLVANIA**

1. LIQUID LEVEL ACQUISITION

Responsible Personnel: Technicians and Geologists

Training Qualifications:

All field personnel involved in liquid level acquisition shall have, as a minimum, completed OSHA 40 HOUR HAZWOPER training, PSM training, and obtained a TWIC Card as well as completing the 3-day minimum field training requirements as specified within the Corporate Health and Safety Plan. Prior to solo performance of liquid levels, all field personnel will have performed a minimum of three site visits under the direct supervision of experienced personnel.

Health and Safety Requirements:

Personal Protective Equipment (PPE) Required:

Level D attire including steel toe/steel shank boots, NOMEX coveralls, and an H2S meter are required to be worn. Based on site conditions, Level C attire may be required. The PPE required to upgrade to Level C may include: nitrile gloves, disposable outerboots, Tyvek coveralls, and a respirator. Safety glasses or hard hats may also be required in certain areas.

Site Controls:

Safety cones and or caution tape should be used in high traffic areas. The "Buddy System" may also be employed in high traffic areas.

Potential Hazards:

Traffic, pinch and trip, chemical (airborne and physical contact) and biological are all likely hazards to be encountered on-site. Additional hazards are mentioned in the site-specific HASP.

Materials and Equipment Necessary for Task Completion:

Electronic oil/water interface probe or conductivity water line, decontamination supplies (liquinox, deionized-distilled water, appropriate containers, scrub brush, and sorbent pads or paper towels), and air monitoring instruments (optional, based on previous site visits).

Methodology:

The task involves the deployment of a liquid sensing probe into a well (in most cases), recording the reading, and decontaminating the probe. The recorded field readings can then be utilized for one of several applications including: well sampling, water table gradient mapping, separate-phase hydrocarbon occurrence, thickness, and or gradient mapping, and various testing procedures.

The proper procedure for liquid level acquisition from a well is as follows:

- 1) The wells should be gauged in order of least to most contaminated based on existing sampling data or separate-phase hydrocarbon occurrence.
- 2) The gauging instrument is decontaminated prior to initial deployment and after each well to prevent cross contamination between wells.
- 3) Decontamination procedures include the following steps:
 - a) Remove gross contaminants with sorbent pad or towel.
 - b) Rinse/scrub equipment with water.
 - c) Scrub equipment in Liquinox[®]/deionized-distilled water solution.
 - d) Double rinse with deionized-distilled water.
 - e) Air dry.
- 4) The well(s) to be gauged may need to be marked off with safety cones and or caution tape in order to protect personnel from auto traffic; the "Buddy System" may also be employed.
- 5) The manhole cover is then lifted off of the well head. A pry bar may be needed to prevent personal injury in the case of large manhole covers.
- 6) The probe is lowered into the well until the instrument signals contact with liquid.
- 7) The corresponding reading is recorded when the instrument signals either water or product. A clear bailer may be used to verify the existence or approximate amount and appearance of product.
- 8) The probe is then retracted from the well and decontaminated accordingly.
- 9) The well is then secured appropriately.
- 10) Note the start and stop time for gauging round in the field book.

2. GROUNDWATER MONITORING PROCEDURES

Responsible Personnel: Technicians and Geologists

Health and Safety Requirements:

Site specific HASP must be completed and reviewed by field personnel. Ambient air monitoring will be performed quarterly at all treatment areas to determine the necessity of PPE upgrade. As a minimum, level "D" attire will be worn.

Training Qualifications:

All field personnel involved in groundwater monitoring shall have, as a minimum completed OSHA 40 HOUR HAZWOPER training and completed the 3 day minimum field training requirements. Prior to groundwater monitoring, all field personnel will have sampled a minimum of three sites under the direct supervision of experienced personnel. Field personnel will also have experience in vapor monitoring techniques and sampling equipment decontamination.

Materials and Equipment Necessary for Task Completion:

A list of equipment required to access, gauge, purge, and sample site monitoring wells is presented below. Also listed are materials necessary to store, label, preserve, and transport groundwater samples.

- Current site map detailing well locations;
- Field data book for recording site data;
- Liquid level gauging device (graduated, optical interface probe);
- Keys and tools to provide well access;
- Appropriate sample containers and labels: volatile samples will be collected in laboratory provided 40 milliliter (ml) glass vials with plastic caps fitted with Teflon[®] lined septa; all sample bottles will be laboratory sterilized and will contain the appropriate preservative, if applicable;
- Appropriate well purging apparatus as determined by volume of groundwater to be purged and compounds to be analyzed;
- Teflon[®] (or equivalent) bottom-loading bailer to extract groundwater sample;
- Clean nylon or polypropylene bailer cord;
- Disposable nitrile sampling gloves;
- Decontamination supplies;
- Calibrated five-gallon bucket and watch or stopwatch to determine discharge rate during purging;

- Blank chain-of-custody forms; and
- Cooler and ice for sample preservation.

Methodology for Three Well Volume Sampling:

Prior to actual site visitation for the groundwater sampling event, the following data will be reviewed to ensure proper preparation for field activities:

- Most recent liquid level data from all wells;
- Most recent analytical data from all wells to determine gauging and sampling sequence; and
- Well construction characteristics.

Each monitoring well to be sampled will be gauged to obtain liquid level data immediately prior to initiation of the sampling process. Refer to Liquid Level Gauging SOP for appropriate well gauging procedures. Liquid level data will be recorded in a field book. Should free-phase petroleum product be detected by the gauging process and verified through inspection in a pre-cleaned acrylic bailer, groundwater sampling will not be conducted at that location.

The sampling procedure will be initiated by purging from the well a minimum of three well volumes, except in cases where the well is pumped dry, as referenced below. Well purging is performed to remove stagnant water and to draw representative water from the aquifer into the well for subsequent sampling and analysis for the established parameters. In extreme cases where a well is pumped dry and/or shows little recharge capacity, the well will be evacuated once prior to sample procurement. Well volume calculations will be based on total well depth as determined during well installation and depth-to-water measurements obtained immediately prior to sampling.

Down-hole pre-purge, post-purge, and sampling water quality readings will be collected. The parameters to be monitored and recorded will include dissolved oxygen, turbidity, pH, specific conductance, redox potential, and temperature.

Well purging can be performed with various equipment including: a dedicated bailer for hand bailing low volumes of water; a surface mounted electric centrifugal pump with dedicated polyethylene tubing; and/or submersible pump (when the depth to water is greater than 20 feet) with dedicated polyethylene tubing. During pumping, the intake will be placed directly below the static water surface and slowly lowered during the purging process. This procedure may not prove necessary in low-yielding wells but is important in high-yielding, permeable strata where

an intake initially placed deep in a well may draw laterally and have little influence in exchanging water from shallower depths within the well bore.

Flow rate during well purging will be approximated by the bucket and stop watch method. The duration of pumping required to remove three well volumes will be calculated directly from this flow rate. All fluids removed during purging will be treated on-site with activated carbon.

The sequence of obtaining site groundwater samples will be based upon available historical site data for existing wells and soil organic vapor analyzer (OVA) readings for newly installed wells. Site wells will be sampled in order from the lowest to highest concentration of water quality indicator parameters based upon the most recent available set of laboratory analyses to reduce the potential for sample cross-contamination. Groundwater samples will not be obtained for analysis from any well containing measurable free product.

The following sequence of procedures will be implemented for the collection of groundwater samples from monitoring wells.

- 1) Establish a clean work area where sampling equipment will not come in contact with the ground or any potentially contaminated surfaces.
- 2) Use a laboratory, pre-cleaned Teflon® sampling bailer for each well.
- 3) Use a clean pair of nitrile gloves.
- 4) Attach an appropriate length of unused, clean nylon or polypropylene cord to the designated sampling bailer.
- 5) Select appropriate laboratory-sterilized sample containers.
- 6) Slowly lower sampling bailer into well until water surface is encountered; continue to lower the sampling bailer into the standing water column to one foot below the water surface.
- 7) Retrieve bailer at a steady rate to avoid excess agitation.
- 8) Visually inspect bailed sample to ensure that no free product or organic detritus has been collected.
- 9) Uncap first designated sample vial and fill from bailer as rapidly as possible but minimizing agitation; secure septum and lid.
- 10) Inspect sealed sample for entrapped air; if air is present within sample vial. Remove lid and repeat vial filling, sealing and inspection process until no air is present.
- 11) Repeat Steps 9 and 10 for the second designated vial; all volatile parameter samples will be collected in duplicate.

- 12) Complete and attach labels to sample containers noting sample collector, date, time, and location of sample; record same data in field book.
- 13) Place samples in ice-filled cooler in such a manner as to avoid breakage. Samples collected for VOC analysis will be maintained at a temperature of 4°C.

Discard gloves and bailer cord and move to next sample location.

Methodology for Low-Flow Purging and Sampling:

For wells that will be Low-Flow purged and sampled, the USEPA Region III Bulletin QAD023: *Procedure for Low-Flow Purging and Sampling of Groundwater Monitoring Wells* will be followed. The following data will be reviewed for each well in order to set the pump intake for the low flow sampling:

- Soil boring (lithologic) log and continuous soil sample PID;
- Well construction log showing the screened interval;
- Identification of the most permeable zone screened by the well;
- Approximate depth to static water;
- Proposed pump intake setting; and
- Technical rationale for the pump intake setting, preferably across from the most impacted/contaminated subsurface interval.

Equipment

Adjustable rate, submersible, bladder pumps in conjunction with Teflon® or Teflon-lined polyethylene tubing for purging and sampling will be used. An alternate set up would include a stainless steel submersible Hurricane Pump with Teflon-lined tubing. The tubing diameter will be between 3/16-inch to 1/2-inch inner diameter and the length of the tubing extended outside the well will be minimized. Flow through cells will be used to evaluate parameters during sampling. Monitoring well information, equipment specifications, water level measurements, parameter readings, and other pertinent information will be recorded during monitoring well purging and sampling.

Sampling Procedure

The following protocol details the low-flow sampling procedure that will be used for sampling the monitoring wells.

1. PID Screening of Well. A PID measurement will be collected at the rim of the well.

immediately after the well cap will be removed and recorded on the sampling form.

2. Depth to Water Measurement. A depth to water measurement will be collected and recorded. To avoid disturbing accumulated sediment and to prevent the inadvertent mixing of stagnant water, measuring the total depth of the well will be done at the completion of sampling on an annual basis.
3. Low Stress Purging Startup. Water pumping will commence at a rate of 100 to 400 milliliters per minute (mL/min). This pumping should cause very little drawdown in the well (less than 0.2-0.3 feet) and the water level should stabilize. Water level measurements are made continuously and will be recorded in milliliters per minute on the sampling form.
4. Low Stress Purging and Sampling. The water level and pumping rate will be monitored and recorded every five minutes during purging, and any pumping rate adjustments will be recorded. During the early phase of purging, emphasis will be placed on minimizing and stabilizing pumping stress, and recording any necessary adjustments. Adjustments, when necessary, will be made in the first 15 minutes of purging. If necessary, pumping rates will be reduced to the minimum capabilities of the pump to avoid well dewatering. If the minimal drawdown exceeds 0.3 feet, but the water level stabilizes above the pump intake setting, purging will continue until indicator field parameters stabilized, as detailed in Step 5 below. If the water level drops below the pump intake setting at the absolute minimum purge rate, the pump will remain in place and the water level will be allowed to recover repeatedly until there will be sufficient water volume in the well to permit the collection of samples.
5. Indicator Field Parameters Monitoring. During well purging, indicator field parameters (DO, turbidity, pH, specific conductance, and redox potential) will be monitored every five minutes (or less frequently, if appropriate). Purging will be considered complete and sampling began when all the aforementioned indicator field parameters had stabilized. Stabilization will be achieved when three consecutive readings, taken at five (5) minute intervals (or less frequently, if appropriate), are within the following limits:
 - DO (± 10 percent);
 - turbidity (± 10 percent);
 - specific conductance (± 3 percent);
 - pH (± 0.1 unit); and
 - redox potential [Eh] ± 10 mv).

Temperature and depth to water will be also monitored during purging. Should any of the parameter-reading components of the flow-through meter fail during sampling; the sampling team will attempt to locate a replacement flow-through meter. If none is available, the

sampling team will measure that parameter with an individual criteria meter. Any other field observations relating to sample quality, such as odor, foaming, effervescence, and sheens, will also be recorded on the sampling form.

6. Collection of Ground Water Samples. Water samples for laboratory analyses will be collected before the groundwater had passed through the flow-through cell by either using a by-pass assembly or by temporarily disconnecting the flow-through cell. All sample containers will be filled by allowing the pump discharge to flow gently down the inside of the container with minimal turbulence. During purging and sampling, the tubing remains filled with water in order to minimize possible changes in water chemistry upon contact with the atmosphere. Methods employed to ensure that the outlet tubing will be filled include (i) adjusting the tubing angle upward to completely fill the tubing and (ii) restricting the diameter of the tubing near the outlet of the tubing.

The order in which samples will be collected is as follows:

- Volatile organics;
- Gas sensitive (e.g., Fe^{+2} , CH_4 , $\text{H}_2\text{S}/\text{HS}$);
- Base/Neutrals or PAHs;
- Total Petroleum Hydrocarbons;
- Total metals;
- Dissolved metals;
- Cyanide;
- Sulfate and chloride;
- Nitrate and ammonia;
- Preserved inorganic;
- Non-preserved inorganic; and
- Bacteria.

Decontamination Requirements:

Numerous practices are employed throughout the processes of site investigation and sampling to assure the integrity of the resulting data. Of particular significance to the procedures of

groundwater measurement and sampling is the limitation, whenever possible, of materials inserted into a well bore and, even more importantly, of materials transferred from well to well.

Many items can be discarded between well sampling and/or gauging locations without significantly impacting project costs. Dedicated sampling equipment which can be discarded between well sampling locations without significantly impacting project costs, will be used whenever possible to preclude decontamination requirements. Sampling equipment included in this category are Teflon[®] bailers, nitrile gloves, and bailer cord. However, other investigative and sampling equipment, including such items as liquid level probes, must be reused from well to well.

The danger in multi-well equipment applications lies in the potential of cross-contamination. While the threat of cross-contamination is always present, it can be minimized through the implementation of a consistent decontamination program during sensitive site measurement and data collection activities. The decontamination procedure is outlined below:

All site equipment used in a multi-well capacity will be decontaminated immediately prior to initial use and between each well. Standard site decontamination procedures for the optical interface probes between wells will be performed according to the following schedule:

- Initial rinse with clean tap water to remove excess residuals;
- Scrub equipment with sponge or clean, soft cloth in a distilled water/Liquinox[®] (or equivalent) solution; and
- Double rinse with deionized/distilled water.

Rinse water generated during decontamination procedures will be treated on-site by passing the water through a bucket filled with activated carbon prior to disposal.

3. SOIL SAMPLING & WELL INSTALLATION

Responsible Personnel: Geologist

Training Qualifications: All field personnel supervising drilling activities shall have completed OSHA 40-Hour training, and three days of field training. Personnel supervising the well installation shall have observed drilling procedures for a minimum of three under the direct supervision of experienced personnel. Field personnel will have experience in operating the following field equipment: interface probe and photo-ionization detector (PID). Personnel should be able to describe soils encountered during drilling for generation of well logs.

Health and Safety Requirements:

A site specific HASP must be completed and reviewed by all field personnel. Prior to deploying a rig to the site, a utility call must be made (i.e. Pennsylvania One-Call) to allow mark-out of known subsurface utilities and associated laterals proximal to the site. Site plans, if available, should be reviewed to document and avoid the location of on-site utilities. No drilling should occur on retail sites within the exclusion zone. This zone is defined as the area between the pumps, the tank field and the station building. The area is excluded from drilling activities due to the likely occurrence of subsurface petroleum distribution lines. After review of all known mapped and marked utilities, a site reconnaissance will be performed to document the location of utility meters and storm sewer drains. In addition, the location of overhead utilities must be documented. After completing the subsurface and overhead utility review, the area to drill may be observed as clear or the location may be adjusted to a "clear" location.

Once the drilling location is established, the area must be marked with cones to alert area traffic of the work area. Other health and safety concerns include slip/trip hazards, working with heavy equipment and overhead work hazards. During drilling activities, a minimum of protective work gloves, steel toed boots, hard hats, and safety goggles must be worn.

A final health and safety requirement includes hand clearing the borehole, prior to advancing the borehole with the drill rig. To ensure the safety of workers, the borehole will be cleared by hand or air knife, to depth of 5 feet below ground surface. This will serve to clear the area of utilities, prior to drilling.

Decontamination Requirements:

All down-hole equipment must be steam cleaned prior to drilling at each boring/well location. All soil sampling equipment must be cleaned with detergent and rinsed with distilled water prior to deployment into the borehole. All well construction materials (i.e. PVC well casing, PVC well screen, sand pack, bentonite seal) should be clean and dedicated to each hole.

Methodology for Borings Outside RCRA Areas in AOI 5:**1) Borehole Advancement**

During soil sampling or well installation activities, a borehole is advanced into the unconsolidated subsurface materials or bedrock via a drill rig (or similar). Various types of drilling methods could be deployed to advance the hole. A description of each drilling method is included below:

a) Hollow Stem Auger

A spiral tool form is used to move material from the subsurface to the surface. A bit at the bottom cuts into the subsurface material. Spiral augers on outside convey the material to the surface while spinning. The center of the auger is hollow like a straw when the inner drive rods and plug are removed. During drilling or formation cutting, the center is filled with rods connected to a plug at the bottom bit. Once the desired drilling depth is reached, the center plug and rods can be pulled out, leaving the hollow augers in place. The hollow augers hold the borehole to remain open for sediment sampling and well installation.

b) Air Rotary

A drill bit at the bottom of rods is used to cut into the subsurface material. Air injected into the drill rods escapes through small holes in the drill bit and conveys the drill cuttings to the surface.

c) Geoprobe®

The geoprobe® sampling allows collection of soil by directly pushing (through hydraulic hammering) a sampling device lined with a plastic macrocore into the soil column.

d) Hand Auger

A stainless steel or aluminum hand auger will be physically advanced to the desired soil sampling depth.

2) Soil Sampling

Soil samples will be obtained for lithologic logging and laboratory analysis for chemical contaminants with one of three different sampling devices: Split barrel spoon sampler, hand auger or Geoprobe® soil sampler. For either method, the sampling devices are lowered through the hollow-stem augers or open borehole to allow sampling of the undisturbed sediments below the auger bit. Soil samples will be collected at intervals which appear to be visually impacted or from intervals which exhibit the highest deflections on the screening device (PID or similar).

a) Split barrel spoon sampler (split spoon)

The split spoon sampler will be driven into the soil column in accordance with ASTM Standard Method D1586 (Reference A6, Appendix E). Soil sampling by split barrel spoon will entail drilling a borehole with a hollow-stem auger to the desired sampling depth (standard five foot intervals). After augering to the desired depth, slowly and carefully lower the split barrel spoon sampler attached to the drill rod extension into the borehole. Drive the sampler into the soil by repeated blows from a 140 Lb. hammer with 30 inch travel. Record the blow counts required to drive the split spoon sampler each successive six inch interval.

Remove sampler for borehole, split barrel open, remove soil sample utilizing a stainless steel knife to trim the top and edges of the sample and containerize sample in appropriate sample jar.

b) Geoprobe®

The geoprobe® liner is dedicated to each soil sampling interval. After retrieval of the sample, the liner may be sliced open and the soil sample can be logged and containerized in the appropriate sample jar. During shallow soil sampling from fine-grained sediments, the geoprobe® can advance the sampler directly into the ground, without the advance of an augered borehole.

c) Hand Auger

The hand auger allows for soil from the desired interval to be collected directly by removing the soil column that is contained in the auger portion of the device.

Methodology for Well Installations:

1) Well Construction

After drilling to the desired depth or the desired interval, permanent monitoring wells can be installed to allow groundwater sampling. In general, wells are constructed with slotted screen, which allows groundwater to flow into the well at the desired monitored interval and well casing, which restricts groundwater flow into the well from undesired interval. In most cases the well materials are constructed of PVC. In conditions where the shallowest groundwater interval is monitored, a single case construction monitoring well is installed. In conditions where multiple water bearing units occur and deep groundwater conditions are selected for monitoring, a double cased well is installed.

a) Single Casing Construction

The construction details of a monitoring well are determined by soil type, depth to groundwater and relative fluctuation of groundwater level. After drilling to the desired depth, a monitoring well is constructed for installation into the evacuated borehole. The well consists of a bottom cap, a length of screen and length of well casing. To determine the length of screen used, seasonal groundwater table or tidal fluctuations should be considered to allow the water table to intercept the well screen throughout the year. The assembled well is then inserted into the borehole.

The annular space between the well screen and subsurface is filled with a sand pack, which consists of clean, sorted sand. The sand pack allows water flow into the well but acts as a

filter to prevent subsurface sediments from silting in the well. The sand pack extends one to two feet above the top of well screen. Above the sand pack, a seal is installed in the annular space between the well casing and the subsurface. The seal is comprised of hydrated bentonite and prevents surface water from infiltrating the well screen. Above the well seal, the annular space is backfilled with drill cuttings or cement. A cap is placed on the top of the well to further prevent infiltration of the surface water. The top of the well is protected with either a stand-up pipe or a locking, flush mount box.

b) Double Casing Construction

In cases where multiple water bearing zones occur, a double case well is installed to allow monitoring of the deeper water bearing zones. Construction of a double cased well is similar to that of a single case well; however, to prevent groundwater infiltration from shallower water bearing zones, a second casing is installed. This type of construction requires drilling two different diameter boreholes.

During drilling through the shallower groundwater zones, large diameter augers/bits are used to create a large diameter borehole. The borehole is advanced through the shallower water bearing area which will not be monitored. An outer casing is installed to seal the deeper monitoring well from infiltration from the shallow water bearing zones. After the outer casing is installed, the borehole is advanced deeper with smaller diameter auger/bit. The outside diameter of second augers fit within the inside diameter of the outer casing. The borehole is advanced to allow monitoring of the deeper water bearing zone. Once the desired depth is obtained, a monitoring well is installed within the outer casing, using similar methods as described in the single casing construction (3a, above). The outside casing prevents shallow groundwater infiltration into the well. The inside casing prevents surface water infiltration into the well.

2) Soil Cutting Handling

Cuttings generated from drilling will be containerized or stock-piled, undercover, until appropriate disposal is determined. In the case the soils are not impacted, the cuttings may remain on-site. Impacted soils will be removed using appropriate hazardous waste handling procedures and disposed of with an approved hazardous waste handler.

3) Well Development

After installation, monitoring wells are developed to remove residual sediments within the well and annular space. Water is pumped from the well a low flow rate (to minimize turbulence within the well and associated sand pack) until groundwater flowing from the well appears relatively free of sediments.

Documentation:

All site activities should be detailed in the site investigators fieldbook. The entry shall include the date, time, weather, address, and persons present on-site. In addition, data required to create well construction logs or boring logs (if no well is constructed) should be collected. This data includes soil type, relative moisture content, depth of water table, observed impact, soil screening measurements (if PID is used), blow counts (if split spoon samples are collected), sample recovery, depth of borehole, length of well screen, length of well casing(s), sand pack interval, well seal interval. The site investigator should identify the relative location and number.

4. NON-AQUEOUS PHASE LIQUID (NAPL) SAMPLING PROCEDURES

Responsible Personnel: Technicians and Geologists

Training Qualifications:

All field personnel involved must have completed OSHA 40 HOUR HAZWOPER training. Prior to NAPL sampling, all field personnel will have worked a minimum of three sites under the direct supervision of experienced personnel. Field personnel will also have experience in sampling and vapor monitoring techniques and sampling equipment decontamination.

Materials and Equipment Necessary for Task Completion:

A list of equipment required to sample NAPL from a monitoring well is presented below:

- Current site map detailing well locations;
- Field data book for recording site data;
- Liquid level gauging device (graduated, optical interface probe);
- Keys and tools to provide well access;
- Appropriate sample containers and labels. NAPL samples will be collected in laboratory provided 40 milliliter (ml) glass vials with plastic caps fitted with Teflon[®] lined septa; all sample bottles will be laboratory sterilized and will contain the appropriate preservative, if applicable. A minimum of 10 ml is required for laboratory analysis. In the case that sufficient volume is not obtained, a swabbing technique (described below) will be used;
- Sorbent pads (required for swabbing technique);
- Teflon[®] (or equivalent) bottom-loading bailer to obtain NAPL sample;
- Clean nylon or polypropylene bailer cord;

- Decontamination supplies;
- H&S supplies (tyvek, nitrile gloves, safety goggles);
- Blank chain-of-custody forms; and
- Cooler and ice for sample preservation.

Health and Safety Requirements:

Site specific HASP must be completed and reviewed by field personnel. As a minimum, modified Level "D" attire will be worn. Individuals performing NAPL sampling are required to wear safety goggles, tyvek suit, and nitrile sampling gloves.

Decontamination Requirements:

During NAPL sampling activities, dedicated sampling equipment (i.e. Teflon[®] bailers, nitrile gloves, and bailer cord) are utilized; thereby, eliminating decontamination requirements. The interface probe, used to record the presence of NAPL and relative thickness prior to sampling, does require decontamination between sampling locations.

All site equipment used in a multi-well capacity will be decontaminated immediately prior to initial use and between each well. Standard site decontamination procedures for the optical interface probes between wells will be performed according to the following schedule:

- Initial rinse with clean tap water to remove excess residuals;
- Scrub equipment with sponge or clean, soft cloth in a distilled water/Liquinox[®] (or equivalent) solution; and
- Double rinse with deionized/distilled water.

Methodology:

Each monitoring well to be sampled will be gauged to obtain liquid level and relative NAPL thickness immediately prior to initiation of the sampling process. Refer to SOP No. 1 for appropriate well gauging procedures. Liquid level data will be recorded in a field book.

Sampling of the NAPL will occur via two different methods: direct sample or swabbing.

The following sequence of procedures will be implemented for the collection of groundwater samples from monitoring wells.

- 1) Establish a clean work area where sampling equipment will not come in contact with the ground or any potentially contaminated surfaces.

- 2) Use a laboratory, pre-cleaned Teflon® sampling bailer for each well.
- 3) Don an unused, clean pair of nitrile gloves.
- 4) Attach an appropriate length of unused, clean nylon or polypropylene cord to the designated sampling bailer.
- 5) Select appropriate laboratory-sterilized sample containers.
- 6) Slowly lower sampling bailer into well until water surface is encountered; continue to lower the sampling bailer into the standing water column to one foot below the water surface.
- 7) Retrieve bailer at a steady rate to avoid excess agitation.
- 8) Visually inspect bailed sample to ensure for relative thickness of NAPL. If sufficient volume is present (>10 ml) place a direct sample of the NAPL into the laboratory vial. If less than 10 ml of NAPL is present, use a sorbent pad to absorb the NAPL from the surface of the groundwater sample. Place is swab sample into the laboratory vial.
- 9) Complete and attach labels to sample containers noting sample collector and date, time, and location of sample; record same data in field book.
- 10) Place samples in ice-filled cooler in such a manner as to avoid breakage. Samples collected for VOC analysis will be maintained at a temperature of 4°C.
- 11) Discard gloves and bailer cord and move to next sample location.

Documentation:

All site activities should be detailed in the site investigators fieldbook. The entry shall include the date, time, weather, address, persons present on-site, and the aforementioned parameters. Only relevant observations should be recorded. The nature of the work being performed is also appropriate.

1.1 Field Procedures for Surface Water Sampling

1.1.1 General

Surface water sampling is performed to obtain samples for surface water bodies that are representative of existing surface water conditions.

Surface water sampling locations for surface water quality and groundwater interaction studies are selected based on the following:

1. Study objectives
2. Location of point surface discharges
3. Non-point source discharges and tributaries
4. Presence of structures (e.g., bridge, dam)
5. Accessibility

During surface water sampling it is important to obtain samples that are not impacted by the re-suspension of sediment produced because of improper or poor surface water sampling techniques.

1.1.2 Surface Water Sample Location Selection

Prior to conducting surface water sampling activities, the first requirement is the consideration and development of surface water sampling locations. It is important that all surface water sampling locations be selected in accordance with the Work Plan.

Wading for surface water samples increases the chances of disturbance of sediments from the floor of the surface water body. When wading for surface water samples be aware of potential safety and health risks. A life vest and safety line must be worn at all times where footing is unstable or when sampling in fast moving or more than 3 feet (0.9 m) deep. A two-person team is required for most surface water sampling activities. If the site conditions require the use of the life vest and safety line, the two people involved in the sampling must be competent swimmers.

Surface water samples must be collected with no suspended sediments. Surface water samples are collected commencing with the furthest downstream location to avoid sediment interference with upstream locations.

1.1.2.1 Rivers, Streams, and Creeks

Surface water samples are generally collected in areas of surface water bodies that are representative of the surface water body conditions. Representative surface water samples will usually be collected in sections of surface water bodies that have a uniform cross section and flow rate. Mixing is influenced by turbulence and water velocity, therefore the selection of surface water sampling locations immediately downstream of a riffle area (i.e., fast flow zone) will ensure good vertical mixing. These locations are also likely areas for deposition of sediment since this occurs in areas of decreased flow velocity.

Surface water sampling locations should not be established in areas near point source discharges. Surface water sampling of these source discharge points can be performed to assess the impact of

these source areas on overall surface water quality. Sample tributaries as close to the mouth as possible. It is important to select surface water sample locations considering the impact downstream, including tributary flow and sediment.

In all instances, properly document all surface water sampling locations. Documentation may include photographs and tie-ins to known structures.

1.1.3 Sampling Equipment and Techniques

When collecting surface water samples, direct dipping of the sample container into the stream or water is acceptable unless the sample container contains preservatives. If preserved, a pre-cleaned unpreserved sample container should be used to collect the surface water sample. The surface water sample is then transferred to the appropriate preserved sample container. When collecting surface water samples, submerge the inverted bottle to the desired sample depth and tilt the opening of the sample container upstream to fill. During surface water sample collection, wading or movement may cause sediment deposits to be re-suspended and can result in biased samples. Wading is acceptable if the stream has a noticeable current and the samples are collected directly in the sample container when faced upstream. If the stream is too deep to wade in or if additional samples must be collected at various depths, additional sampling equipment will be required. Surface water samples should be collected about 6 inches (15 cm) below the surface, with the sample bottles being completely submerged. Taking the surface water sample at this depth eliminates the collection of floating debris in the sample container.

Surface water sample collection where the flow depth is less than 1 inch (<2.5 cm) requires the use of special equipment to eliminate sediment disturbance. Surface water sampling may be conducted with a container then transferred to the appropriate sample container, or collection may be performed using a peristaltic pump. A small excavation in the stream bed to create a sump for sample collection can also be considered but should be prepared in advance to allow all the sediment to settle prior to surface water sampling activities.

Teflon™ bailers can be used for surface water sampling if it is not necessary to collect surface water samples at specific depths. A bottom loading bailer with a check ball is sufficient. When the bailer is lowered through the water, the water is continually displaced through the bailer until the desired depth is reached. The bailer is retrieved and the check ball prohibits the release of the collected surface water sample. Bailers are not suitable in surface water bodies with strong currents, or where depth-specific sampling is required.

For discrete and specified depth surface water sampling, and the parameters to be monitored do not require a Teflon™ coated sampling device, a standard Kemmerer or Van Dorn sampler can be used. The Kemmerer sampler is a brass cylinder with rubber stoppers that leave the sampler ends open while the sampler is being lowered. The sampler is lowered in a vertical position to allow water to pass through. The Van Dorn sampler is plastic and is lowered in a horizontal position. For both samplers, a messenger is sent down a rope when the sampler has reached the required depth. The messenger causes the stopper on the sampler to close. The sampler is then retrieved and the surface water sample can be collected through a valve. DO sample bottles can be filled by allowing overflow using a rubber tube attached to the valve. During depth-specific surface water sampling, take care not to disturb bottom sediments.

Glass beakers or stainless steel cups may also be used to collect surface water samples if parameter interference does not occur. The beaker or cup must be rinsed at least three times with the surface water sample prior to sample collection.

All equipment must be thoroughly decontaminated.

1.1.4 Field Notes for Surface Water Sampling

Record daily surface sampling activities, describe surface water sampling locations, sampling techniques, and, if applicable, provide a description of photographs taken. Visual observations are important and provide valuable information when interpreting surface water quality results.

Observations include:

1. Weather conditions
2. Stream flow directions
3. Stream physical conditions (width, depth, etc.)
4. Tributaries
5. Effluent discharges
6. Impoundments
7. Bridges
8. Railway trestles
9. Oil sheens
10. Odors
11. Buried debris
12. Vegetation
13. Algae
14. Fish and other aquatic life
15. Surrounding industrial areas

The following factors should be considered for surface water sampling:

1. **Predominant Surrounding Land Use:** Observe the prevalent land use type in the vicinity and note any other land uses in the area which, although not dominant, may potentially affect surface water quality.
2. **Local Watershed Erosion:** Note the existing or potential erosion of soil in the local watershed and its movement into the stream. Erosion can be rated through visual observation of watershed stream characteristics including increases or decreases in turbidity.
3. **Local Watershed Non-Point Source Pollution:** This refers to problems or potential problems other than erosion and sedimentation. Nonpoint source pollution can be diffuse agricultural and urban runoff. Other factors may include feed lots, wetlands, septic systems, dams, impoundments, and mine seepage.
4. **Estimated Stream Width:** The estimated distance from shore at a transect representative of the stream width in the area.

5. Estimated Stream Depth: Riffle (rocky area), run (steady flow area), and pool (still area). Estimate the vertical distance from the water surface to the bottom of the surface water body at a representative depth at three locations.
6. High Water Mark: Estimate the vertical distance from the bank of the surface water body to the peak overflow level, as indicated by debris hanging in bank or flood plain vegetation, and deposition of silt. In instances where bank flow is rare, high water marks may not be evident.
7. Velocity: Record or measure the stream velocity in a representative run area.
8. Dam Present: Indicate the presence or absence of a dam upstream or downstream of the surface water sampling location. If a dam is present, include specific information detailing the alteration of the surface water flow.
9. Channelized: Indicate if the area surrounding the surface water sampling location is channelized.
10. Canopy Cover: Note the general proportion of open to shaded areas which best describes the amount of cover at the surface water sampling location.

1.2 References

For additional information pertaining to surface water sampling, the user of this manual may reference the following:

ASTM D5358	Practice for Sampling with a Dipper or Pond Sampler
ASTM D4489	Practices for Sampling of Waterborne Oils
ASTM D3325	Practice for the Preservation of Waterborne Oil Samples
ASTM D4841	Practice for Estimation of Holding Time for Water Samples Containing Organic and Inorganic Constituents
ASTM D4411	Guide for Sampling Fluvial Sediment in Motion
ASTM D4823	Guide for Core-Sampling Submerged, Unconsolidated Sediments
ASTM D3213	Practice for Handling, Storing, and Preparing Soft Undisturbed Marine Soil
ASTM D3976	Practice for Preparation of Sediment Samples for Chemical Analysis
ASTM E1391	Guide for Collection, Storage, Characterization, and Manipulation of Sediments for Toxicological Testing
ASTM D4581	Guide for Measurement of Morphologic Characteristics of Surface Water Bodies
ASTM D5906	Guide for Measuring Horizontal Positioning During Measurements of Surface Water Depths
ASTM D5073	Practice for Depth Measurement of surface water

Sediment Sampling Standard Operating Procedures

Introduction

Sediment sampling is conducted to obtain samples that are representative of existing chemical and/or physical conditions of sediment.

Equipment Decontamination

On environmental sites, sediment sampling equipment (e.g., split spoons, trowel, spoons, shovels, bowls, dredges, corers, scoops) are typically cleaned as follows:

1. Wash with clean potable water and laboratory detergent, using a brush as necessary to remove particulates.
2. Rinse with tap water.
3. Rinse with deionized water.
4. Air dry for as long as possible.

Additional or different decontamination procedures may be necessary if sampling for some parameters, including volatile organic compounds (VOCs) and metals.

Sample Site Selection

Before any sampling is conducted, the first requirement is to consider suitable sampling locations. Sampling locations should be selected in accordance with the Work Plan. Wading for sediment samples in lagoons, lakes, ponds, and slow-moving rivers and streams must be done with caution since bottom deposits are easily disturbed. Sampling must only be attempted where safe conditions exist and samples must be collected from undisturbed sediments. All sediment samples are to be collected commencing with the most downstream sample to avoid sediment interference with other downstream samples. A life vest and safety line should be worn in all cases where footing is unstable or where water is fast moving or over 3 feet (0.85 m) in depth. A second person may also be required for most of the sampling scenarios.

Rivers, Streams, and Creeks

Sediment samples may be collected along a cross-section of a river or stream in order to adequately characterize the bed material, or from specific sediment deposits as described in the Work Plan. A common procedure is to sample at quarter points along the cross-section of the sampling site selected. Samples may be composited as described in the Work Plan. Samples of dissimilar composition (e.g., grain size, organic content) should not be combined.

Representative samples can usually be collected in portions of the surface water body that have a uniform cross-section and flow rate. Since mixing is influenced by turbulence and water velocity, the selection of a site immediately downstream of a riffle area (e.g., fast flow zone) are likely areas for deposition of sediment since the greatest deposition occurs where stream velocity slows.

A site that is clear of immediate point sources (e.g., tributaries and industrial and municipal effluents) is preferred for the collection of sediment samples unless the sampling is being performed to assess these sources.

Sampling Equipment and Techniques

General

Any equipment or sampling technique(s) [e.g., stainless steel, polyvinyl chloride (PVC)] used to collect a sample is acceptable so long as it provides a sample which is representative of the area being sampled and is consistent with the Work Plan.

Sediment Sampling Equipment and Techniques

A variety of methods may be used to collect sediment samples from a stream, river, or lake bed. Dredging (Peterson, Ponar, Van Veen), coring and scooping are acceptable sediment sample collection techniques. Precautions shall be taken to ensure that a representative sample of the targeted sediment is collected. Caution should be exercised when wading in shallow water so as not to disturb the area to be sampled. Samplers should be selected based on the interval to be sampled, type of sediment/sludge (silt, sand, gravel), and required sample volume. More than one sampler is often required to implement a sampling program at a site. The following describes some of these methods. Manufacturers information should be consulted to determine the limitations of each type of sampling equipment.

Dredging

The **Peterson dredge** is best used for rocky bottoms, in very deep water, or when the stream velocity is rapid. The dredge should be lowered slowly as it approaches the bottom, so as to not disturb the lighter sediments.

The **Ponar dredge** is similar to the Peterson dredge in size and weight. The Ponar dredge is a "clam-shell" type unit that closes on contact with the river/lake bottom. Depending on the size of the unit, a winch is required for larger units, whereas smaller units are available for lowering by a hand line. Once retrieved, the unit is opened and the sample extracted using a sample scoop or spoon. The unit has been modified by the addition of side plates and a screen on top of the sample compartment. This permits water to pass through the sampler as it descends.

The **Ponar grab** sampler functions by the use of a spring-latch-messenger arrangement. The sampler is lowered to the bottom of the water body by means of a rope, then the messenger is sent down to trip the latch causing the sampler to close on the sediments. The sampler is then raised slowly to minimize the disturbance of the lighter sediments. Sediment is then placed into a stainless steel bowl, homogenized, and placed into the appropriate sample container (if collecting for VOC parameters, fill the VOC jars before homogenization).

Corers

Core samplers are used to obtain vertical columns of sediment. Many types of coring devices are available, depending on the depth of water from which the sample is to be collected, the type of bottom material, and the length of core to be obtained. They vary from hand-push tubes to weight or gravity-driven devices to vibrating penetration devices.

Coring devices are useful in contaminant monitoring due to the minimal disturbance created during descent. The sample is withdrawn intact, allowing the removal of only those layers of interest. Core liners consisting of plastic or Teflon may also be added, thereby reducing the potential for sample contamination and maintaining a stratified sample. The samples may be shipped to the lab in the tubes in which they were collected. The disadvantage of coring devices is that only a small sampling surface area and sample size is obtained, often necessitating repetitive sampling in order to collect the required amount of sediment for analysis. It is also often difficult to extract the sediment sample back out through the water column without losing the sample.

The core tube is pushed/driven into the sediment until only 4 inches (10 cm) or less of tube is above the sediment-water interface. When sampling hard or coarse sediments, a slight rotation of the tube while it is pushed will create greater penetration and reduce compaction. Cap the tube with a Teflon plug or a sheet of Teflon. The tube is then slowly withdrawn, keeping the sample in the tube. Before pulling the bottom part of the core above the water surface, it must be capped.

Scooping

The easiest way to collect a sediment sample is to scoop the sediment using a stainless steel spoon or scoop. This may be done by wading into the stream or pond and, while facing upstream (into the current), scooping the sample from along the bottom in an upstream direction. This method is only practical in very shallow water.

Mixing

Sediment samples collected for chemical analysis should be thoroughly mixed (except for VOCs) in a stainless steel bowl prior to placement in the appropriate sample container. Standard procedures exist for preparation of sediment samples (ASTM D3976). These should be followed or the laboratory informed of applicable procedures.

Air Monitoring

Prior to sediment/sludge sampling, measure the breathing space above the sample location with a photoionization detector (PID), should the potential for volatiles be present, and use a hydrogen sulfide meter should hydrogen sulfide be present. Repeat these measurements during sampling. If either of these measurements exceed any of the air quality criteria established in the HASP, air purifying respirators (APRs) or supplied air systems will be required.

Sample Location Tie-In/Surveying

The recording of the sample locations and depth on the site plan is extremely important. This may be accomplished by manual measurement (i.e., swing ties), global positioning system (GPS) survey, or stadia methods. Manual measurements for each sample location should be tied into three permanent features (e.g., buildings, utility poles, hydrants). Diagrams with measurements should be included in the field book.

Field Notes

A bound field book is used to record daily activities, describe sampling locations and techniques, and describe photographs (if taken). Visual observations are important, as they may prove invaluable in interpreting water or sediment quality results. Observations shall include (as applicable) weather, stream flow conditions, stream physical conditions (width, depth, etc.),

tributaries, effluent discharges, impoundments, bridges, railroad trestles, oil sheens, odors, buried debris, vegetation, algae, fish or other aquatic life, and surrounding industrial areas. The following observations should be considered:

- **Predominant Surrounding Land Use:** Observe the prevalent land use type in the vicinity (noting any other land uses in the area which, although not predominant, may potentially affect water quality).
- **Local Watershed Erosion:** The existing or potential erosion of soil within the local watershed (the portion of the watershed that drains directly into the stream) and its movement into a stream is noted. Erosion can be rated through visual observation of watershed and stream characteristics. (Note any turbidity observed during water quality assessment.)
- **Local Watershed Non-point Source Pollution:** This item refers to problems and potential problems other than siltation. Non-point source pollution is defined as diffuse agricultural and urban runoff (e.g., stormwater runoff). Other compromising factors in a watershed that may affect water quality are feedlots, wetlands, septic systems, dams and impoundments, and/or mine seepage.
- **Estimated Stream Width:** Estimate the distance from shore at a transect representative of the stream width in the area.
- **Estimated Stream Depth:** Riffle (rocky area), run (steady flow area), and pool (still area). Estimate the vertical distance from water surface to stream bottom at a representative depth at each of the three locations.
- **High Water Mark:** Estimate the vertical distance from the stream bank to the peak overflow level, as indicated by debris hanging in bank or floodplain vegetation, and deposition of silt or soil. In instances where bank overflow is rare, a high water mark may not be evident.
- **Velocity:** Record an estimate of stream velocity in a representative run area (see Section 12.0).
- **Dam Present:** Indicate the presence or absence of a dam upstream or downstream of the sampling station. If a dam is present, include specific information relating to alteration of flow.
- **Channelized:** Indicate whether the area around the sampling station is channelized.
- **Canopy Cover:** Note the general proportion of open to shaded area which best describes the amount of cover at the sampling station.
- **Sediment Odors:** Disturb sediment and note any odors described (or include any other odors not listed) which are associated with sediment in the area of the sampling station.
- **Sediment Oils:** Note the term which best describes the relative amount of any sediment oils observed in the sampling area.
- **Sediment Characteristics:** Note the grain size, color, consistency, layering, presence of biological organisms, man-made debris, etc. in accordance with standard ASTM soil description protocols.
- **Sediment Deposits:** Note those deposits described (or include any other deposits not listed) which are present in the sampling area. Also indicate whether the undersides of rocks not deeply embedded are black (which generally indicates low dissolved oxygen or anaerobic conditions).

References

For additional information pertaining to this topic, the user of this manual may reference the following:

ASTM D5358	Practice for Sampling with a Dipper or Pond Sampler
ASTM D4489	Practices for Sampling of Waterborne Oils
ASTM D3325	Practice for the Preservation of Waterborne Oil Samples
ASTM D4841	Practice for Estimation of Holding Time for Water Samples Containing Organic and Inorganic Constituents
ASTM D4416	Guide for Sampling Fluvial Sediment in Motion
ASTM D4823	Guide for Core-Sampling Submerged, Unconsolidated Sediments
ASTM D3213	Practice for Handling, Storing, and Preparing Soft Undisturbed Marine Soil
ASTM D3976	Practice for Preparation of Sediment Samples for Chemical Analysis
ASTM E1391	Guide for Collection, Storage, Characterization, and Manipulation of Sediments for Toxicological Testing
ASTM D4581	Guide for Measurement of Morphologic Characteristics of Surface Water Bodies
ASTM D5906	Guide for Measuring Horizontal Positioning During Measurements of Surface Water Depths
ASTM D5073	Practice for Depth Measurement of Surface Water
ASTM D5413	Test Methods for Measurement of Water Levels in Open-Water Bodies